

STATE OF KANSAS
STATE CORPORATION COMMISSION


15-039-20235-00-00

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Decatur County, Sec. 20 Twp. 1S Rge. (E) 26 (W)
Location as "NE/CNW/SW" or footage from lines C SW SE
Lease Owner Okmar Oil Company
Lease Name Bles Well No. 1
Office Address 1130 Vickers-KSB&T Bldg., Wichita
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed June 8, 19 72
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced June 8, 19 72
Plugging completed June 8, 19 72
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes (W. L. Nichols of Morland)

Name of Conservation Agent who supervised plugging of this well

Producing formation Depth to top Bottom Total Depth of Well 3480 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface	0	300'	8-5/8"	300'	None
	Casing					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Heavy Mud from Total Depth to 1100 Feet,
110 sax Cement; Mud to 330 Feet, 30 sax
Cement; Mud to 40 Feet, Plug Bridged and
10 sax Cement to Base of Cellar; 2 sax
Cement in Rat Hole. Job Completed @ 6 A.M.

RECEIVED
STATE CORPORATION COMMISSION
JUN 13 1972
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor HOWCO
Address Box 339, Hays, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

Clarence Michael of Sage Drilling Co. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Clarence Michael
500 Bitting Building, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 12th day of June 19 72

My commission expires November 26, 1974.

Louise K. Whitted
Louise K. Whitted - Notary Public.

15-039-20235-00-00

DRILLERS LOG

BLEES NO. 1

RECEIVED
STATE CORPORATION COMMISSION
JUN 13 1972
07-13-1972
CONSERVATION DIVISION
Wichita, Kansas


CASING RECORD:	OPERATOR: Okmar Oil Company	DESCRIPTION:
8-5/8" @ 300' w/225 sax cement	CONTRACTOR: Sage Drilling Co.	C SW SE Sec. 20-1S-26W Decatur County, Kans.
TOTAL DEPTH: 3480'	COMMENCED: June 2, 1972	ELEVATION: 2476KB
	COMPLETED: June 8, 1972	

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface Soil	0	314	
Shale	314	968	
Sand	968	1045	
Shale & Sand	1045	1155	
Shale	1155	1610	
Sand	1610	1705	
Shale	1705	1929	
Anhydrite	1929	1957	
Red Bed & Shale	1957	2370	
Shale & Lime	2370	2695	
Lime & Shale	2695	3310	
Lime	3310	3419	
Lime & Shale	3419	3480	D&A

I certify that this is a true and correct copy of the above log to the best of my knowledge.

SAGE DRILLING CO., INC.

BY Clarence Michael
Clarence Michael



Subscribed and sworn to before me this 12th day of June, 1972.

Louise K. Whitted
Louise K. Whitted, Notary Public

My commission expires:
November 26, 1974.