

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-039-20171-00-00

LEASE NAME Huff "D"

WELL NUMBER #1

SPOT LOCATION C NE NE

SEC. 20 TWP. 1S RGE. 26 ~~K00X~~ (W)

COUNTY Decatur

Date Well Completed 8-11-70

Plugging Commenced 9-18-85

Plugging Completed 9-19-85

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR TGT Petroleum Corp.

ADDRESS 209 E. William - Wichita, Ks.

PHONE # (316) 262-6489 OPERATORS LICENSE NO. 5118

Character of Well Oil
 (Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dist. #6 - Hays, Ks.

Is ACO-1 filed? No If not, is well log attached? Yes

Producing formation Lansing Depth to top 3240 bottom 3321 T.D. 3460

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Surface		0	300	8 5/8	300'	None
		0	3459	4 1/2	3459'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Dug out braden head. At inj. rate of 5 bpm @ 300#, mixed & pumped 50 sacks cement/w/5 sacks hulls. Pumped another 250 sacks. Tied into surface & pumped 100 sacks. Pres. up to 200#. Closed annulus in. Tied back to casing, released 4 1/2" wiper plug. Pumped another 50 sacks of cement & started staging. Mixed another 25 sacks. Released another wiper plug & tied back to surface pipe. Mixed & pumped 25 sacks. Squeezed off/w/200#. Closed annulus in. Pumped remainder of cement - total (over) (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor TGT Petroleum Corp. License No. 5118

Address 209 E. William - Wichita, Ks.

STATE OF Kansas COUNTY OF Sedgwick, ss.


B. Lynn Herrington (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well, and I certify that the same are true and correct, so help me God.

(Signature) [Signature]
 (Address) 209 E. William - Wichita, Ks.

OCT 7 1985
 10-07-1985
 CONSERVATION DIVISION
 WICHITA, KANSAS

SUBSCRIBED AND SWORN TO before me this 4th day of October, 1985

My Commission expires: May 17, 1989



Notary Public
 Judith K. Moser

of 525 sacks. Pres. up to 400#. Staged for 10 min. Pres. to 300#. Held okay.
Closed casing in.

RECEIVED
MAY 19 1964
U.S. DEPARTMENT OF AGRICULTURE
WASHINGTON, D.C.

15-039-20171-00-00

WELL LOG

Company: Rosen Oil Corporation
 Suite 260-70 Sutton Place
 Wichita, Kansas 67202

Lease: #1 Huff 'D'
 C NE NE, Section 20-1-26W
 Decatur County, Kansas

Total Depth: 3460' Elevation: 2464 K.B.

Contractor: Slawson Drilling Company, Inc.

Commenced: August 6, 1970

Completed: August 11, 1970

Casing: 8 5/8" at 300' with 250 sx cement
 4 1/2" at 3459' with 150 sx cement


0-300	Surface Clay
300-1918	Shale & Shells
1918-1945	Anhydrite
1945-2370	Shale & Shells
2370-2757	Shale & Lime
2757-3291	Lime & Shale
3291-3460	Lime
3460	Total Depth

STATE OF KANSAS)
) SS:
 COUNTY OF SEDGWICK)

I, Maxine V. Starr, of the Slawson Drilling Company, Inc., upon oath state that the above and foregoing is a true and correct copy of the log of the Rosen Oil Corporation, #1 Huff 'D' well.

Maxine V. Starr
 MAXINE V. STARR

Subscribed and sworn to before me this 13th day of August, 1970.



Linda R. Sparr
 Linda R. Sparr, Notary Public

RECEIVED
 STATE CORPORATION DEPARTMENT
 AUG 13 1970