



15-039-20265-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 9 1973 5-9-73  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Joe Weber of Abercrombie Drilling, Inc., has this  
date requested permission to plug the following described well:

Mr. Weber guarantees payment of the plugging fee.

Operator's full Name: Abercrombie, Drilling, Incorporated,

Complete Address: 801 Union Center, Wichita, Kansas.

Lease Name: Richards Well No. 2

Location: NW-NE Sec. 22 Twp. 1 Rge. (E)(W) 26

County: Decatur Total Depth 3580' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Weber as instructed to plug the well as follows:

211'--8 5/8" Surface casing, cement circulated with 170 Sx. (6 3/4" Hole).  
Top of Dakota section @ 935'.

Circulate hole with heavy mud. Pull DP to 1160' and displace 70 Cu. Ft.  
cement thru DP. Pull DP to 245' and displace 25 Cu. Ft. cement thru DP.  
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to  
bottom of cellar.

Very truly yours,

A. L. Nichols  
Conservation Division Agent