

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
FEB 13 1970
CONSERVATION DIVISION
Wichita, Kansas
02-13-1970

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-039-20139-00-00

Operator's Full Name A. L. Abercrombie, Incorporated,
Complete Address 801 Union Center Building, Wichita, Kansas.
Lease Name Huff Well No. G-2
Location 140' So. of CSW-NW Sec. 21 Twp. 1 Rge. (E) (W) 26
County Decatur Total Depth 3573'
Abandoned Oil Well Gas Well Input Well SWD Well D & A
Other well as hereafter indicated
Plugging Contractor Abercrombie Drilling, Incorporated,
Address 801 Union Center Building, Wichita, Kansas. License No.
Operation Completed: Hour 10:30 AM Day 11 Month 2 Year 1970

The above well was plugged as follows:

319'--7 5/8" OD Surface casing, cement circulated. (6 1/4" Hole).
Top of Dakota section @ 980'.

Circulated hole with heavy mud. Pulled DP to 1200' and displaced 65 Sx. cement thru
DP from 1200' to 875'. Pulled DP to 335' and displaced 15 Sx. cement thru DP from
335' to 260'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *A. L. Abercrombie*
Well Plugging Supervisor

INVOICED
DATE 2/13/70
INV. NO. 1420-W