

KANSAS

Y

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
06-12-1972
JUN 12 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

15-039-20235-00-00

Operator's Full Name Okmar Oil Company,
Complete Address 1130 Vickers KSB&T Building, Wichita, Kansas.
Lease Name Blees Well No. 1
Location CSW-SE Sec. 20 Twp. 1 Rge. (E) (W) 26
County Decatur Total Depth 3480'
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated
Plugging Contractor Sage Drilling Company, Incorporated,
Address 500 Bitting Bldg., Wichita, Kansas License No.
Operation Completed: Hour 6:00 AM. Day 8 Month 6 Year 1972

The above well was plugged as follows:

300'--8 5/8" Surface casing, cement circulated with 225 Sx.
Top of Dakota section @ 875'.

Circulated hole with heavy mud. Pulled DP to 1100' and displaced 110 Cu. Ft. cement
thru DP from 1100' to 775'. Pulled DP to 330' and displaced 30 Cu. Ft. cement thru
DP from 330' to 255'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *R. L. Dehals*
Well Plugging Supervisor

INVOICED

DATE 6-13-72
INV. NO. 5846-W