

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
08-02-1974  
AUG 2 1974  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

15-039-20143-00-01

Operator's Full Name TGT Petroleum Corporation

Complete Address 209 East William St. Wichita, Kansas 67202

Lease Name Hoover Well No. 1

Location 440' FNL & 440' FWL NW Sec. 20 Twp. 1 Rge. (E) (W) 26

County Decatur Total Depth 3360'

Abandoned Oil Well XX Gas Well      Input Well      SWD Well      D & A ✓

Other well as hereafter indicated     

Plugging Contractor Kelse Pipe Pulling

Address Box 176, Chase, Kansas License No. 683

Operation Completed: Hour 6:30 P Day 31 Month 7 Year 1974

The above well was plugged as follows:

Total Depth 3360' 8 5/8 csg set at 309' ewe 150 sk.

4 1/2 csg set at 3350' ew 150 sx.

4 1/2 csg PBSD 3308' & perf. (3171-3277)

Set 4 1/2 wood plug at 3000' -poured 10' sand -dumped 3 sk cmt W/dump bailer. (2960-3000)

Cutoff and recovered 1200' of 4 1/2 csg.

Pumped down 8 5/8 csg with 15 sk gel & water -60 sk cem. -15 sk gel & water -100 lbs hulls & 50 sk cement.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo J. Messing  
Well Plugging Supervisor

INVOICED

DATE 8/2/74

INV. NO. 9650-W