

KANSAS

*4*  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

15-039-20143-00-00

RECEIVED  
STATE CORPORATION COMMISSION  
02-26-1970  
FEB 26 1970  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Okmar Oil Company,

Complete Address 1130 Wichita Plaza Building, Wichita, Kansas.

Lease Name Hoover Well No. 1

Location SE NW NW NW  
440' SNL & 440' EWL of Sec. 20 Twp. 1 Rge. (E) (W) 26

County Decatur Total Depth 3551'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X

Other well as hereafter indicated       

Plugging Contractor B & B Drilling, Incorporated,

Address 207 Petroleum Building, Wichita, Kansas. License No.       

Operation Completed: Hour 11:00 AM Day 24 Month 2 Year 1970

The above well was plugged as follows:

303'--8 5/8" Surface casing, cement circulated with 185 Sx.  
Top of Dakota section @ 950'.

Circulated hole with heavy mud. Pulled DP to 1150' and displaced 100 Sx. cement thru  
DP from 1150' to 825'. Pulled DP to 310' and displaced 25 Sx. cement thru DP from  
310' to 235'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to  
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: M. D. Nichols  
Well Plugging Supervisor

DATE 2/27/70  
INV. NO. 1509-W