

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
08-2-1974
AUG 2 1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

15-039-20189-00-00

Operator's Full Name TGT Petroleum Corporation

Complete Address 209 E. William St., Wichita, Kansas 67202

Lease Name Richards Well No. 1

Location C NE NW Sec. 21 Twp. 1 Rge. (E) (W) 26

County Decatur Total Depth 3390'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Knight Casing Pulling

Address Box 176, Chase, Kansas License No. 683

Operation Completed: Hour 1:30 P Day 31 Month 7 Year 1974

The above well was plugged as follows:

Total Depth 3390' 8 5/8 csg set at 254' cwe 200 sk.

5 1/2 csg set at 3389' cw 100 sk. Top perf. (3166')

Set 5 1/2 wood plug at 3100' -poured 10' sand -dumped 2 sk cem W/dump bailer.

Set 5 1/2 wood plug at 3000' -poured 10' sand -dumped 4 sk cmt W/dump bailer. (3000-2960)

Cutoff and recovered 1519' of 5 1/2 csg/

Pumped down 8 5/8 csg with 15 sk gel & water -40 sk cem. -15 sk gel & water -released

8 5/8 csg & pumped 50 sk cem W/100 lbs hulls.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo J. Marney
Well Plugging Supervisor

INVOICED

DATE 8/27/74

INV. NO. 9651-W