

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-055-20666-00-02  
Spot: SWNWSE Sec/Twnshp/Rge: 2-23S-31W  
1650 feet from S Section Line, 2310 feet from E Section Line  
Lease Name: CARR Well #: 2-2  
County: FINNEY Total Vertical Depth: 4897 feet

Operator License No.: 32198  
Op Name: PETROSANTANDER (USA) INC.  
Address: 6363 WOODWAY STE. 350  
HOUSTON, TX 77057

CIBP Size: feet: 4680  
PROD Size: 5.5 feet: 4873 WITH 150 SX CMT  
SURF Size: 8.625 feet: 472 WITH 275 SX CMT *# 159<sup>15</sup>*

Well Type: WSW UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/29/2004 9:00 AM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: PETE KUNEYL Company: PETROSANTANDER Phone: (620) 275-2388

Proposed Plugging Method: PER KCC RULES AND REGULATIONS. CASING LEAK @ 2200'. 300# HULLS W/35 SX CMT ON TOP SET AT 3800'. 250 SX (EST) FROM 2200' TO SURFACE.

Plugging Proposal Received By: KEVIN STRUBE Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 03/29/2004 11:45 AM KCC Agent: KEVIN STRUBE

Actual Plugging Report:

PBTD 4840'. PUMPED DOWN 5 1/2" 400# HULLS - 35 SX CMT - 13 SX GEL - 190 SX CMT. WELL ON VACUUM. SHUT DOWN 1 HOUR. PUMPED 65 SX CMT. WELL STILL ON VACUUM. SHUT IN WELL. TOPPED OFF WITH 75 SX CMT & 100# HULLS. PUMPED DOWN 8 5/8" X 5 1/2" ANNULUS 10 SX CMT. SHUT IN AT 500#.

Perfs:

Top	Bot	Thru	Comments
4773	4776		
3966	3978		
3926	3961		
3912	3920		
3885	3904		

RECEIVED  
APR 02 2004  
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

Plugged through: CSG

District: 01

RECEIVED  
APR - 1 2004  
KCC Dodge City

Signed Kevin D Strube  
(TECHNICIAN) *SA*

INVOICED  
DATE 4-1-04  
VV. NO. 2004061379