

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. MARKET, ROOM 2078
WICHITA, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

TYPE OR PRINT
NOTICE: Fill out Completely
and return to cons. div.
office within 30 days.

API NUMBER 15-167-21,961-00-00
LEASE NAME Loving
WELL NUMBER 1
2640 ft. from S Section Line
4290 ft. from E Section Line
SEC. 9 TWP. 14 RGE. 13 (E) or (W)
COUNTY Russell
Date Well Completed 12-27-1982
Plugging Commenced 3/18/04
Plugging Completed 3/19/04

LEASE OPERATOR Starr F. Schlobohm
ADDEESS 47 Michawanic Road, #3D, Sanbornville, NH 03872-3787
PHONE # (603) 522-9760 OPERATORS LICENSE NO. 4952
Character of well oil

(Oil, Gas, D&A, SWD, input, Water Supply Well)
The plugging proposal was approved on 3/18/04 (date)
by Herb Deines (XCC District Agent's Name)

I s ACO-1 filed? yes if not, Is well log attached not available to us

Producing Formation Tarkio Sands Depth to Top 2,385' Bottom 2,441' T.D. 2490

Show depth and thickness of all water, oil and gas formations
OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Surf				7"	502	none
Tarkio Sands	Oil & water	2,385'	2,441'	4 1/2"	2477	1702

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set

Sand at 2297, bail 4 sks cem. Rip pipe loose at 1702, pull to 1400, pump 80 cem. with 3 hulls. Pull to 840, pump 25 cem with 1 hulls. Pull to 520, pump 25 cem. with 1 hulls. Pull to 200 and circulate cem. with 25 sacks. Lay rest of pipe down.

Name of Plugging Contractor Quality Well Service, Inc. License No. 31925
Address 401 West Main, Lyons, KS 67554

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Starr F. Schlobohm

STATE OF New Hampshire COUNTY OF Carroll, ss.

Starr F. Schlobohm (Employee of Operator) or (Operator) of
above - described well, being first duly sworn on oath, says: That I have knowledge of the facts
statements, and matters herein contained and the log of the above described well as filled that
the same are true and correct, so help me God.

(Signature) *Starr F. Schlobohm*
(Address) 47 Michawanic Road, #3D
Sanbornville, NH 03872-3787

SUBSCRIBED AND SWORN TO before me 29th day of March, 2004

JoAnne MacDonald
Notary Public

My commission Expires: 3/14/07

Form CP-4
Revised 05-88

JoAnne M. MacDonald
NOTARY PUBLIC OF NEW HAMPSHIRE
My Commission Expires Aug. 14, 2007

RECEIVED
APR 01 2004
KCC WICHITA

15-167-21961-00-00

Quality Well Service, Inc.

Invoice

**401 West Main
Lyons, KS 67554**

**RECEIVED
APR 01 2004
KCC WICHITA**

Date	Invoice #
3/22/2004	526

Bill To
Starr F. Schlobohm 47 Michawanic Road #3D Sanbornville, NH 03872-3787

P.O. No.	Terms	Lease Name
	net	Loving #1

Description	Qty	Rate	Amount
Rig Time	13	128.00	1,664.00T
Trucking		90.00	90.00T
sand		35.00	35.00T
cement	4	9.00	36.00T
rips	1	140.00	140.00T
torch		35.00	35.00T
water truck	4.5	58.00	261.00T
backhoe	3.5	62.00	217.00T
phone calls		5.00	5.00T
clerical fees		10.00	10.00T
wiping rubber		15.00	15.00T
3/18/04 Drove to location, rigged up and checked hole. Dug cellar and pit, sanded bottom and loaded hole. Drove in.			
3/19/04 Drove to location, tore head down and checked hole. Sand at 2297, bailed 4 sacks cement. Set floor, pulled slips, cut surface off. Ripped 1702, worked free. Pulled to 1400, pumped 80 sacks with 3 hulls. Pulled to 840, pump 25 sacks with 1 hulls. Pull to 520, pumped 25 sacks cement with 1 hulls. Pull to 200', circulate cement with 25 sacks. Layed rest of pipe down and tore down. Loaded out, emptied pit and filled cellar and pit in.			
Subtotal			\$2,508.00
Sales Tax (6.3%)			\$158.00
Total			\$2,666.00