

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-039-20,171-00-00 (of this well) 6/86
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR TGT Petroleum Corp. OPERATORS LICENSE NO. 5118

ADDRESS 209 E. William - Wichita, Ks. 67202 PHONE # (316) 262-6489

LEASE (FARM) Huff "D" WELL NO. 1 WELL LOCATION C NE NE COUNTY Decatur

SEC. 20 TWP. 1S RGE. 26 ~~(E) (W)~~ TOTAL DEPTH 3460 PLUG BACK TD 3342

Check One:

OIL WELL GAS WELL _____ D & A _____ SWD or INJ WELL _____ DOCKET NO. _____

SURFACE CASING SIZE 8 5/8" SET AT 300' CEMENTED WITH 250 SACKS

CASING SIZE 4 1/2" SET AT 3459' CEMENTED WITH 150 SACKS

PERFORATED AT 3240'-44', 3280'-85', 3316'-21', 3405'-08', 3413'-19'

CONDITION OF WELL: GOOD _____ POOR _____ CASING LEAK JUNK IN HOLE

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL This well has a break-in at approx. 1400'. Has solid bridge of drilling mtl. and formation immediately below the break-in. I propose we squeeze thru casing with 250 sx., followed with wiper plug to approx. 900', then perf. at 850' and squeeze with 175 sx., followed by wiper plug to 100', then fill remainder of casing from top. Hook into annulus and pump 100 sacks.

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? _____
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN 7:00 AM Sept. 3, 1985 - Tuesday

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Mark Danner

PHONE # (316) 463-3524

ADDRESS Burrton, Ks.

PLUGGING CONTRACTOR TGT Petroleum Corp. LICENSE NO. 5118

ADDRESS Wichita, Ks. PHONE # (316) 262-6489

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT

SIGNED: B. Lynn Herrington

(Operator or Agent)

B. Lynn Herrington, Ex. Vice-Pres.

DATE: August 22, 1985

CONSERVATION DIVISION
Wichita, Kansas

RECEIVED

08-23-1985
AUG 23 1985

6



JOHN CARLIN
MICHAEL LENNEN
MARGALEE WRIGHT
EITH R. HENLEY
JUDITH A. McCONNELL
ERIAN J. MOLINE

Governor
Chairman
Commissioner
Commissioner
Executive Secretary
General Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
200 Colorado Derby Building
202 West 1st Street
WICHITA, KANSAS 67202-1286

THIS NOTICE

15-039-20171-00-00

NOV 23 1985

August 23, 1985

EXPIRES

WELL PLUGGING NOTICE

Huff "D" #1
C NE NE
Sec. 20-1S-26W
Decatur County

TGT Petroleum Corp.
209 E. William
Wichita, KS 67202

Gentlemen:

This is your notice to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This notice is void after ninety (90) days from the above date.

Sincerely,

William R. Bryson, Director

Please submit your proposal for plugging the above captioned well to
DIST. #6 1014 Cody Hays, KS 67601 913-628-1200
five days prior to plugging the well (KAR-82-3-113).