

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-23893-00-00  
Spot: SWNE Sec/Twnshp/Rge: 28-15S-17W  
4290 feet from S Section Line, 990 feet from E Section Line  
Lease Name: JACOBS-SCHULTE Well #: 1  
County: ELLIS Total Vertical Depth: 3600 feet

Operator License No.: 5059  
Op Name: BRUNGARDT, F. C. D/B/A EAGLE OIL C  
Address: P. O. BOX 109  
VICTORIA, KS 67671

PROD Size: 5.5 feet: 3599 150 SX CMT  
SURF Size: 8.625 feet: 244 175 SX CMT

8117<sup>00</sup>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/31/2004 9:00 AM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: FRANK BRUNGARDT Company: EAGLE OIL COMPANY Phone: (785) 735-2207

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 10% gel - 500# hulls.  
8 5/8" - 244' w/175 sxs cement. 5 1/2" - 3599' w/150 sxs cement.  
DV tool set (depth n/a).

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 03/31/2004 12:45 PM KCC Agent: EDWIN SCHUMACHER

Actual Plugging Report:

Tied onto 8 5/8" x 5 1/2" annulus - pressured up 700 P.S.I. - backside full.  
Tied onto 5 1/2" casing - pumped 300 sxs 60/40 pozmix - 10% gel with 500# hulls.  
Ordered additional cement - broke connection - top of cement at approximately 200'.  
Pumped additional 15 sxs 60/40 pozmix - 10% gel with cement to surface.

Perfs:

Top	Bot	Thru	Comments
3504	3506		
3489	3491		
3470	3472		
3446	3448		

RECEIVED  
APR 02 2004  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed

Ed Schumacher

(TECHNICIAN)

INVOICED

DATE

4-2-04

INV. NO.

200406375

MAR 31 2004

NOTICE

EAGLE OIL COMPANY  
 BOX 295  
 VICTORIA, KS 67671


#1 JACOBS-SCHULTE

28-15-17W  
 SW NE NE

CONTR REVLIN DRILLING CTY ELLIS

GEOL \_\_\_\_\_ FIELD RAJEWSKI

ELV 1975 KB SPD 6/5/84 CARD ISSUED 9/20/84 IP P 20 BQ & 2.22 BWPD  
1970 GL LKC 3446-3506 OA



DRLRS	Tops	Depth/Datum	API 15-051-23,893
			8 5/8" 244/175SX, 5 1/2" 3599/150SX, DV TOOL SET (DEPTH NA)
			DST (1) 3350-90, (LKC) / 30-30-30-30, REC 180' M, PRESSURES NA
ANH	1124+	851	DST (2) 3440-75 (LKC) / 60-30-60-30, REC 10' GSY OCM, 111' HVY GSY OCM, 11' HVY GSY CO, PRESSURES NA.
B/ANH	1165+	810	MICT-CO, PF (LKC) 3446-48, 3504-06 W/ 4 SPF, AC 2500G (15%) & 2000G (28%), SWB DWN, GSO, SET 2" TBG AT 3596, POP, P 20 BQ & 2.22 BWPD 7/7/84
NO OTHER TOPS AVAILABLE			
RTD	3600-	1625	

COPYRIGHT 1984  
 INDEPENDENT OIL & GAS SERVICE, INC.  
 WICHITA, KANSAS