

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
9 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-145,2010000

LEASE NAME Tanbarger

WELL NUMBER 1

330 Ft. from S Section Line

1920 Ft. from <sup>W</sup>X Section Line

SEC. 13 TWP. 23 RGE. 15W (E) or (W)

COUNTY Pawnee

Date Well Completed 12-14-1988

Plugging Commenced 3-29-04

Plugging Completed 3-31-04

APR 06 2004  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.  
KCC WICHITA

LEASE OPERATOR DUDREY PRODUCTION C & B Oper., Inc

ADDRESS P.O. Box 65 St. Hohn, Kansas 67579

PHONE# (620) 549-3234 OPERATORS LICENSE NO. 8045

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Is plugging proposal was approved on \_\_\_\_\_ (date)

by Richard Lacey (KCC District Agent's Name).

Is SACO-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 4200'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
<u>Sand</u>				<u>8-5/8"</u>	<u>282'</u>	<u>None</u>
<u>Grat</u>				<u>5-1/2"</u>	<u>4090'</u>	<u>2110'</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs are used, state the character of same and depth placed, from feet to feet each set. Plugged off bottom with sand to 3730' and 4 sacks cement. Cut pipe loose @2110', pulled up to 1050', pumped 10 sacks gel and 50 sacks cement, pulled up to 300', pumped 50 sacks cement, pulled up to 40' and topped off with 20 sacks cement. 60/40 pos, 6% gel.  
Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Dudrey Production C & B Oper., Inc.

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed and the same are true and correct, so help me God.


(Signature) Mike Kelso

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 5th day of April, 2004

Jane Derynburg  
Notary Public

My Commission Expires:



Form CP  
Revised 05-