



# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 12 1970  
CONSERVATION DIVISION  
Wichita, Kansas

2-12-1970

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Bob Delaney of Leben Drilling, Incorporated has this date requested permission to plug the following described well:

Mr. Delaney guarantees payment of the plugging fee.

Operator's full Name: Leben, et al.,

Complete Address: 200 Sutton Place, Wichita, Kansas.

Lease Name: Carter Well No. 1

Location: CSW-SE Sec. 33 Twp. 1 Rge. (E)(W) 26

County: Decatur Total Depth 3660 Oil Well     

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Delaney was instructed to plug the well as follows:

250'--8 5/8" Surface casing, cement circulated with 200 Sx.  
Top of Dakota section @ 900'.  
Circulate hole with heavy mud. Pull DP to 1125' and displace 100 Sx.  
cement thru DP. Pull DP to 275' and displace 25 Sx. cement thru DP.  
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom  
of cellar.

Very truly yours,

Conservation Division Agent