

State of Kansas



15-039-20284-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

MAY 13 1974

5-13-74

CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Joe Weber of Abercrombie Drilling, Inc., has this date requested permission to plug the following described well:

Mr. Weber guarantees payment of the plugging fee.

Operator's full Name: A. L. Abercrombie, Incorporated,

Complete Address: 801 Union Center, Wichita, Kansas.

Lease Name: Chambers Well No. 5

Location: SW-SW-SW Sec. 29 Twp. 1 Rge. (E)(W) 26

County: Decatur Total Depth 3665' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Weber was instructed to plug the well as follows:

219'--8 5/8" Surface casing, cement circulated with 140 Sx. (6 3/4" Hole).  
Top of Dakota section @ 925'.

Circulate hole with heavy mud. Pull DP to 1150' and displace 70 Cu. Ft. cement thru DP. Pull DP to 245' and displace 30 Cu. Ft. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to bottom of cellar.

Very truly yours,

*W. L. Nichols*

Conservation Division Agent