

KANSAS DRILLERS LOG


API No. 15 — 039 — 20,274-00-00
 County Number

S. 32 T. 15 R. 26 ^{EW}

Loc. SW NE SE

County Decatur

640 Acres
N



Locate well correctly

Elev.: Gr. 2571

DF 2577 KB 2579

Operator
Abercrombie Drilling

Address 801 Union Center
Wichita, Kansas 67202

Well No. 1 Lease Name Railsback

Footage Location
1650 feet from (N) (S) line 990 feet from (E) (W) line

Principal Contractor Abercrombie Drilling, Inc. Geologist Jack K. Wharton

Spud Date October 1, 1973 Total Depth 3693' P.B.T.D.

Date Completed October 8, 1973 Oil Purchaser

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface Csg.	12 1/4"	8-5/8"	---	248'	Common	150	2% gel

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

Size	Setting depth	Packer set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

INITIAL PRODUCTION

Date of first production Producing method (flowing, pumping, gas lift, etc.)

RATE OF PRODUCTION PER 24 HOURS
 Oil bbls. Gas MCF Water bbls. Gas-oil ratio CFPB

Disposition of gas (vented, used on lease or sold) Producing interval(s)

RECEIVED
 STATE CORPORATION COMMISSION
 OCT 11 1973
 CONSERVATION DIVISION
 Wichita, Kansas

10-11-73

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:

Operator

Abercrombie Drilling, Inc.

Well No.

1

Lease Name

Railsback

Dry Hole

S 32 T 1S R 2 ^{XX} W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Clay & Shale	0	252	Anhydrite	2029
Shale	252	1110	B/Anhydrite	2060
Sand	1110	1200	Heebner	3327
Shale	1200	1635	Toronto	3362
Sand & Shale	1635	2029	Lansing	3373
Anhydrite	2029	2060	Granite Wash	3686
Shale	2060	2470	T.D	3693
Shale & Lime	2470	2690		
Lime	2690	2891		
Lime & Shale	2891	3070		
Lime	3070	3693		
Rotary T.D.		3693		
<p>DST #1 (3333-3380) 30"-30"-30"-30". Rec. 25' SOCM. IFP 45-58#, IBHP 468#, FFP 62-64#, FBHP 416#.</p> <p>DST #2 (3384-3402) 30"-30"-30"-30". Rec. 3' drlg. mud w/few specks oil. IFP 18-20#, IBHP 20#, FFP 20-20#, FBHP 20#.</p> <p>DST #3 (3384-3416) 30"-45"-30"-30". Rec. 60' drlg. mud. IFP 47-52#, IBHP 1165#, FFP 76-83#, FBHP 1089#.</p> <p>DST #4 (3520-3546) 20"-30"-30"-30". Rec. 5' drlg. mud. IFP 20-20#, IBHP 20#, FFP 20-20#, FBHP 20#.</p>				

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

Jack K. Wharton
 Jack K. Wharton
 Signature

Geologist

Title

October 10, 1973

Date