

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 16 1973 11-16-1973  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

15-039-20278-00-00

Operator's Full Name Abercrombie Drilling, Incorporated,

Complete Address 801 Union Center, Wichita, Kansas.

Lease Name Kelly Well No. 1

Location CNE-NE Sec. 28 Twp. 1 Rge. (E) (W) 26

County Decatur Total Depth 3654'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X

Other well as hereafter indicated       

Plugging Contractor Above

Address        License No.       

Operation Completed: Hour 12:30 AM Day 15 Month 11 Year 1973

The above well was plugged as follows:

228'--7 5/8" Surface casing, cement circulated. (6 3/4" Hole).  
Top of Dakota section @ 875'.

Circulated hole with heavy mud. Pulled DP to 1100' and displaced 70 Cu. Ft. cement  
thru DP from 1100' to 775'. Pulled DP to 250' and displaced 30 Cu. Ft. cement thru  
DP from 250' to 150'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.  
cement to bottom of cellar.

**INVOICED**

I hereby certify that the above well was plugged as herein stated.

DATE 11/16/73  
INV. NO. 8173-W

Signed: N. L. Nichols  
Well Plugging Supervisor