

15-039-2 0234-00-00

Form CP-3  
Rev. 6-4-68

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 18 1972  
S-18-72  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name John O. Farmer, Incorporated,

Complete Address 370 West Wichita Avenue, Russell, Kansas.

Lease Name Mapes Well No. 1

Location GSW-SW Sec. 27 Twp. 1 Rge. (E) (W) 26

County Decatur Total Depth 3631'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X

Other well as hereafter indicated       

Plugging Contractor Above

Address        License No.       

Operation Completed: Hour 3:45 AM Day 15 Month 5 Year 1972

The above well was plugged as follows:

219'--8 5/8" Surface casing, cement circulated with 150 Sx.  
Top of Dakota section @ 900'.

Circulated hole with heavy mud. Pulled DP to 1125' and displaced 110 Cu. Ft. cement  
thru DP from 1125' to 800'. Pulled DP to 245' and displaced 30 Cu. Ft. cement thru  
DP from 245' to 170'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.  
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: K. L. Nichols  
Well Plugging Supervisor

INVOICED

DATE 5/18/72  
INV. NO. 5725-W