

KANSAS

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 12 1970  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

15-039-20138-00-00

2-12-1970

Operator's Full Name Leben et al.,-  
Complete Address 200 Sutton Place, Wichita, Kansas.  
Lease Name Carter Well No. 1  
Location CSW-SE Sec. 33 Twp. 1 Rge. (E) (W) 26  
County Decatur Total Depth 3660'  
Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X  
Other well as hereafter indicated         
Plugging Contractor Leben Drilling, Incorporated,  
Address Box #486, Great Bend, Kansas. License No.         
Operation Completed: Hour 4:00 AM Day 9 Month 2 Year 1970

The above well was plugged as follows:

250'--8 5/8" Surface casing, cement circulated with 200 Sx.  
Top of Dakota section @ 900'.

Circulated hole with heavy mud. Pulled DP to 1125' and displaced 100 Sx. cement thru  
DP from 1125' to 800'. Pulled DP to 275' and displaced 25 Sx. cement thru DP from  
275' to 200'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to  
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: M. L. Dackels  
Well Plugging Supervisor

DATE 2/12/70  
INV. NO. 1416-W