

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

15-039-20284-00-00

Operator's Full Name A. L. Abercrombie, Incorporated.

Complete Address 801 Union Center, Wichita, Kansas.

Lease Name Chambers Well No. 5

Location SW-SW-SW Sec. 29 Twp. 1 Rge. (E) (W) 26

County Decatur Total Depth 3665' 3655'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Abercrombie Drilling, Incorporated.

Address Above License No.

Operation Completed: Hour 10:45 AM Day 9 Month 5 Year 1974

The above well was plugged as follows:

219'--8 5/8" Surface casing, cement circulated with 140 Sx. (6 3/4" Hole).
Top of Dakota section @ 925'.

Circulated hole with heavy mud. Pulled DP to 1150' and displaced 70 Cu. Ft. cement
thru DP from 1150' to 825'. Pulled DP to 245' and displaced 30 Cu. Ft. cement thru
DP from 245' to 170'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Received
5-14-74

Signed: W. L. Nichols
Well Plugging Supervisor

DATE 5/14/74
INV. NO. 9109-W