

15-039-20105-00-00

R

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

8-18-69
RECEIVED
STATE CORPORATION COMMISSION
AUG 18 1969
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Donald C. Slawson,

Complete Address 408 One-Twenty Building, Wichita, Kansas.

Lease Name Keley Kelley Well No. A-1

Location CNE-SE Sec. 31 Twp. 1 Rge. (E) (W)26

County Decatur Total Depth 3688'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Slawson Drilling Company, Incorporated,

Address 408 One-Twenty Building, Wichita, Kansas. License No.

Operation Completed: Hour 3:30 PM Day 7 Month 8 Year 1969

The above well was plugged as follows:

249'--8 5/8" Surface casing, cement circulated with 165 Sx.
Top of Dakota section @ 1250'.

Circulated hole with heavy mud. Pulled DP to 1475' and displaced 100 Sx. cement thru
DP from 1475' to 1150'. Pulled DP to 275' and displaced 25 Sx. cement thru DP from
275' to 200'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 8-18-69

INV. NO. 324-W

Signed: M. L. Nichols
Well Plugging Supervisor