

15-039-20274-00-00
KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
OCT 11 1973
CONSERVATION DIVISION
Wichita, Kansas
10-11-73

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Abercrombie Drilling, Incorporated,

Complete Address 801 Union Center, Wichita, Kansas.

Lease Name Railsback Well No. 1

Location CSW-NE-SE Sec. 32 Twp. 1 Rge. (E) (W) 26

County Decatur Total Depth 3693'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Above

Address License No.

Operation Completed: Hour 6:30 AM Day 8 Month 10 Year 1973

The above well was plugged as follows:

243'--8 5/8" Surface casing, cement circulated with 150 Sx. (6 3/4" Hole).
 Top of Dakota section @ 925'.

Circulated hole with heavy mud. Pulled DP to 1150' and displaced 70 Cu. Ft. cement
 thru DP from 1150' to 825'. Pulled DP to 245' and displaced 30 Cu. Ft. cement thru
 DP from 245' to 170'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
 cement to bottom of cellar.

INVOICED hereby certify that the above well was plugged as herein stated.

DATE 10/11/73

Signed: N. L. Nichols
Well Plugging Supervisor

INV. NO. 8006-42