

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

60660-00-00
15-039-05000-00

FORMATION PLUGGING RECORD

OR

Strike out upper line
when reporting plug-
ging off formations.

Decatur County. Sec. 3 Twp. 1S Rge. (E) 27 (W)

Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NE NE NE

Lease Owner Helmerich & Payne, Inc.

Lease Name Sauvage Well No. 1

Office Address 415 Philtower, Tulsa, Oklahoma.

Character of Well (completed as Oil, Gas or Dry Hole) Dry hole

Date well completed 3-22-43 19

Application for plugging filed 5-15-43 19

Application for plugging approved 5-19-43 19

Plugging commenced 5-19-43 19

Plugging completed 5-11-43 19

Reason for abandonment of well or producing formation Dry hole

If a producing well is abandoned, date of last production None 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well C. T. Alexander

Producing formation None Depth to top Bottom Total Depth of Well 3685 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS


CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
K. C. (S.O.)	Water	3311	3510	8 5/8	293	None
Granite Wash	Water	3649	3682	5 1/2	3518	1248
Granite	None	3682	3685			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

5 1/2" casing set at 3518', cemented with 150 sacks. Halliburton plug pumped to 3484 and never drilled out. Perforated casing 3464 - 3458, 3391-3387', 3310-3306 and 3314-3310. Dumped 14 sacks cement and filled to 3285'. Shot casing at 2532', 1436 and 1308 and not free. Shot at 1248 and free. Hole was mudded prior to shooting and hole was mudded as casing was pulled. Set bridge at 290' and dumped ten sacks on top. Filled hole to top. Put cement cap of 4 sacks in top of surface casing.

PLUGGING
FILE SEC. 3 TWP. 1S RGE. 27W
BOOK PAGE 75 LINE 8



(If additional description is necessary, use BACK of this card.)

Correspondence regarding this well should be addressed to Helmerich & Payne, Inc.
Address 415 Philtower, Tulsa, Oklahoma.

STATE OF Okla., COUNTY OF Tulsa, ss.

1, C. M. Copeland (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C M Copeland

415 Philtower Building, Tulsa, Oklahoma.
(Address)

SUBSCRIBED AND SWORN to before me this 28th day of May, 19 43

My commission expires July 22, 1943

Sue Griffin
Notary Public.

Sauvage #1
NE/4 NE/4 NE/4 of Section 3-13-37N
DeCATUR County, Kansas
Holmerich & Payne, Inc.

15-039-0066000-00

Commenced: February 15, 1943
 Completed: March 22nd., 1943

Surface clay, shale and shells	0	174	Soft lime	3290	3296
Sand	174	193	Shale	3296	3312
Shale, clay and shells	193	255	lime	3312	3340
Shale and shells	255	370	Shale	3340	3363
lime	370	610	lime	3363	3372
Shale and shells	610	750	lime and red shale	3372	3383
Shale and shells	750	985	lime	3383	3403
Shale and streaks pyrite	985	1005	Shale	3403	3422
Shale	1005	1030	lime and shale	3422	3426
Sand	1030	1110	Shale	3426	3436
Sand and shale	1110	1160	Shale and lime	3436	3438
White sand	1160	1265	lime	3438	3502
Sandy shale and shells	1265	1570	lime and shale	3502	3550
Shale and shells	1570	1685	Shale	3550	3550
Sand	1685	1700	Shale streaks of lime	3550	3610
Shale, shells and sand	1700	1805	Shale	3610	3654
Shale and shells	1805	2005	lime	3654	3640
Anhydrite	2005	2025	Gumbo shale	3640	3648
lime	2025	2035	Sand	3648	3649
lime and shale	2035	2100	Granite wash	3649	3682
Shale and shells	2100	2180	Granite	3682	3683
Sticky shale	2180	2225			
Shale	2225	2450	TOTAL DEPTH	3685	
Shale and shells	2450	2475			
Shale	2475	2523			
lime	2523	2605			
Shale, sticky	2605	2655			
Shale	2655	2665			
lime	2665	2685			
Broken lime	2685	2750			
Shale	2750	2800			
Shale and streaks of chert	2800	2825			
Broken lime	2825	2960			
lime	2960	3105			
lime, shale and red rock	3105	3120			
Soft lime	3120	3145			
Shale	3145	3151			
White lime	3151	3190			
lime	3190	3204			
Shale	3204	3225			
lime and shale	3225	3256			
Soft white lime	3256	3266			
lime	3266	3272			
lime and shale	3272	3290			

CASING RECORD

3-5/8" casing set at 295' and cemented with 225 sacks of cement.

5-1/2" casing set at 3015' and cemented with 150 sacks of cement.

PLUGGING

FILE SEC. 3-1-R 270
 BOOK PAGE 75 LINE 8

06-19-1943

STATE OF OKLAHOMA)

COUNTY OF TULSA)

I hereby affirm that the above and foregoing is a true and correct copy of the log of our Sauvage Well #1, located in the Northeast Quarter of the Northeast Quarter of the Northeast Quarter of Section 3, Township 1 South, Range 17 West, DeCATUR County, Kansas.

HOLMERICH & PAYNE, INC.

William Goodhue
 Treasurer

Subscribed and sworn to before me, a Notary Public, this 22nd. day of March, 1943.

Sue Griffin
 Notary Public

My commission expires
 July 22nd, 1943.