

STATE OF KANSAS
STATE CORPORATION COMMISSION

FORM CP-1

Rev. 03/92

RECEIVED
MAR 31 2004
KCC WICHITA

CONSERVATION DIVISION

130 S. Market, Room 2078
Wichita, Kansas 67202

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API #: 15-083-21489-0000 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spu or completion date

WELL OPERATOR: McCoy Petroleum Corporation
(owner/company name)

KCC LICENSE # 5003
(operator's) *6/04*

ADDRESS: 8080 E. Central CITY: Wichita

STATE: Kansas ZIP CODE: 67206 CONTACT PHONE: 316-636-2737

LEASE: Brumfield Trust 'A' 50'E of SENE WELL#: 1-36 Section 36 Township 22s Range 25w
SE NE SPOT LOCATION/QQQQ COUNTY: Hodgeman

1980 FEET (in exact footage) FROM North LINE OF SECTION (NOT Lease Line)
660 FEET (in exact footage) FROM East LINE OF SECTION (NOT Lease Line)

Check One: Oil Well _____ Gas Well _____ D&A XX SWD/ENHR WELL _____ Docket # _____
CONDUCTOR CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS
SURFACE CASING SIZE 8-5/8" SET AT 214' KB CEMENTED WITH 150 SACKS
PRODUCTION CASING SIZE None SET AT _____ CEMENTED WITH _____ SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS:
ELEVATION 2467 G.L. 2476 K.B. T.D. 4775 P.B.T.D. _____ Anhydrite Depth 1309-1352
(Stone Corral Formation)

CONDITION OF WELL: GOOD XX POOR _____ CASING LEAK _____ JUNK IN HOLE _____

PROPOSED METHOD OF PLUGGING:
Received plugging orders on 03/27/04 at 9:00 pm from Steve Pfeifer. Plugged in following manner beginning
at 11:45 pm on 03/29/04: Used 195 sx of 60/40 Poz; 6% Gel; 1/4# Floseal. Heavy mud in hole; bottom plug
at 1685' - 50sx, 2nd plug at 870' - 80sx, 3rd plug at 240' - 40sx, top plug at 40'-10 sx, cemented to surface.
Rathole - 15sx, no mousehole. Plug down at 2:30 am on 03/30/04. Allied Cementing ticket #18283.

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes (YES,NO) IS ACO-1 FILED? ? (YES,NO)
If not explain why: _____

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Name: Lanny Saloga/Gary M. Talbott Phone#: (620) 672-9508
Address: P.O. Box 1006 City: Pratt State: Kansas

PLUGGING CONTRACTOR: Sterling Drilling Company KCC LICENSE #: 5142
(company name) (contractor's) *6/04*

Address: P.O. Box 1006 City: Pratt State: Kansas Zip 67124

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) Plugged well at 2:30 am on March 29, 2004. *Plugged*

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY: Operator X Agent _____

DATE: 03/30/04 AUTHORIZED OPERATOR OR AGENT: Gary M. Talbott
(signature) Gary M. Talbott, Agent for Operator

RECEIVED

MAR 31 2004

KCC WICHITA

Sterling Drilling Company, Rig #4

Box 1006, Pratt, Kansas 67124-1006
Office Phone (620) 672-9508, Fax 672-9509

SAMPLE LOG

Brumfield Trust 'A' 1-36

LOCATION:	SE NE	Section	36	T 22s	R 25w
API:	15-083-21489-0000	Hodgeman County, Kansas			

OWNER: McCoy Petroleum Corporation	COMMENCED: 03/20/04	
CONTRACTOR: Sterling Drilling Company, Rig #4	COMPLETED: 03/30/04	
TOTAL DEPTH:	DRILLER 4775 FEET	Ground Elevation: 2467
	LOGGER 4782 FEET	KB Elevation: 2476

LOG

0 -	4 FEET	Surface Soils
4 -	180 FEET	Sand and Clay
180 -	1650 FEET	Redbeds
1650 -	1685 FEET	Anhydrite (Driller's)
1685 -	2400 FEET	Shales and Salt
2400 -	4775 FEET	Limestone/Shales

CASING RECORDS

Surface Casing:

Spud @ 3:30 pm on 03/20/04. Drilled 12-1/4" hole to 220'. Ran 5 joints of new 23# 8-5/8" surface casing tally 203.20' set at 214.20' KB, Cemented with 150 sx Common; 3% CC, 2% Gel. Plug down at 8:30 pm on 03/20/04. Cement did circulate. Allied Cementing ticket #18257. Welded straps on bottom 3 joints & welded collars on remainder.

Production Casing:

Received plugging orders on 03/27/04 at 9:00 pm from Steve Pfeifer. Plugged in following manner beginning at 11:45 pm on 03/29/04: Used 195 sx of 60/40 Poz; 6% Gel; 1/4# Floseal. Heavy mud in hole; bottom plug at 1685' - 50sx, 2nd plug at 870' - 80sx, 3rd plug at 240' - 40sx, top plug at 40'-10 sx, cemented to surface. Rathole - 15sx, no mousehole. Plug down at 2:30 am on 03/30/04. Allied Cementing ticket #18283. SDC reported to KCC on 03/30/04.

DEVIATION SURVEYS

3/4 degree(s) at	220	feet
1-3/4 degree(s) at	4775	feet