

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
200 Colorado Derby Building  
Wichita, Kansas 67202

FORM CP-1  
Rev. 2/89

**WELL PLUGGING APPLICATION FORM**  
(File One Copy)

API NUMBER 15-039-20,855-00-00 (of this well).  
(This must be listed; if no API# was issued, please note drilling completion date.)

WELL OWNER/OPERATOR A. L. Abercrombie, Inc. OPERATOR'S LICENSE NO. 5393

ADDRESS 150 N. Main, Suite 801, Wichita, KS 67202 PHONE # (316) 262-1841

LEASE (FARM) Sumner Constructive WELL NO. 1 WELL LOCATION C W/2 SE SW COUNTY Decatur

SEC. 32 TWP. 1S RGE. 26 (~~E~~~~XX~~~~W~~) TOTAL DEPTH 3537' PLUG BACK TD         

**Check One:**

OIL WELL  GAS WELL  D & A  SWD or INJ WELL  DOCKET NO.         

SURFACE CASING SIZE 8 5/8" SET AT 281' CEMENTED WITH 200 SACKS

CASING SIZE          SET AT          CEMENTED WITH          SACKS

PERFORATED AT         

CONDITION OF WELL: GOOD  POOR  CASING LEAK  JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Circulate heavy mud in hole. 1st plug at 2035'-30 sx. 2nd

plug at 1397'-100 sx. & 1 sack Flocel, 3rd plug at 330'-50 sx. 4th plug at 40'-10 sx. with

wiper plug. Rathole-15 sx. Mousehole-15 sx. All cement 60/40 pozmix, 6% gel, 3% cc.

(If additional space is needed use back of form.)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED?  IS ACO-1 FILED?  Yes  
(If not explain.)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN at 5:00 a.m. on 8-13-89

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE  
RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

William Craig, Sr. PHONE # (913) 674-2876

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 25 1989

ADDRESS Box 297, Hill City, KS 67642

PLUGGING CONTRACTOR Abercrombie Drilling, Inc. LICENSE NO. 5422

CONSERVATION DIVISION  
Wichita, Kansas 825-89

ADDRESS 150 N. Main, Suite 801, Wichita, KS 67202 PHONE # (316) 262-1841

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT.

SIGNED: Jack H. Wharton  
(Operator or Agent)

DATE: 8-24-89