

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-21961-00-00
Spot: SESWNW Sec/Twnshp/Rge: 9-14S-13W
2640 feet from S Section Line, 4290 feet from E Section Line
Lease Name: LOVING Well #: 1
County: RUSSELL Total Vertical Depth: 2490 feet

Operator License No.: 4952
Op Name: SCHLOBOHM, STARR F.
Address: 47 MICHAWANIC ROAD #3D
SANBORNVILLE, NH 03872

PROD Size: 4.5 feet: 2477 60 SX CMT
SURF Size: 7 feet: 502 175 SX CMT

\$ 80⁹³

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/19/2004 1:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: JOHN L DRISCOLL Company: SCHLOBOHM, STARR F. Phone: (785) 483-9580

Proposed
Plugging
Method:

Plugging Proposal Received By: CASE MORRIS Witness Type: NONE
Date/Time Plugging Completed: 03/19/2004 2:30 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

Sanded to 2297' and dumped 4 sxs cement.
Cut off at 1702'.
Pulled to 1400' - pumped 80 sxs 60/40 pozmix - 10% gel cement with 300# hulls.
Pulled to 843' - pumped 25 sxs cement with 100# hulls.
Pulled to 520' - pumped 25 sxs cement with 100# hulls.
Pulled to 200' - circulated with 25 sxs cement.

Perfs:

Top	Bot	Thru	Comments
2399	2405		
2375	2383		

RECEIVED
APR 06 2004
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed Case Morris
(TECHNICIAN)

INVOICED

DATE 4-6-04
NO. 2004061395

APR 02 2004

A. SCOTT RITCHIE
 125 N. MARKET, #950 #1 LOVING 9-14-13W
 WICHITA, KS 67202 SE SW NW
 CONTR GLACIER DRILLING COMPANY CTY RUSSELL
 GEOL _____ FIELD HALL-GURNEY (1/8 N)
 ELV 1852 K_B SPD 8/18/82 CARD ISSUED 1/20/83 IP P 8 BO & 97 BWPD
 TARK 2375-2405 0A
 API 15-167-21,961

+		+
+	+	+
+		+

SMP	Tops	Depth Datum	7" 502-175SX; 4 1/2" 2477 60SX
ANH	808	+ 1044	NO DSTS
B ANH	843	+ 1009	MIC - CO, PF (TARK SD) 2375-2383, 2399-2405, W / 2 SPF, AC
IND CV	2321	- 469	500G, FRAC 500 BBLS GEL AC & 150 SX SD, FL DWN 800', SWB
GR HAV	2364	- 512	DWN & REC 175 BF, SWB 30 BFPH / 3 HRS, FL 1100' DWN, SWB
1ST TARK SD	2377	- 525	DWN, SWB AVG 25.71 BFPH, NSO / 7 HRS, 1400' FIH, NSO,
2ND TARK SD	2396	- 544	R&T, POP, P 8 BO & 97 BWPD
TARK LS	2435	- 583	
WILLARD SH	2455	- 603	
RTD	2490	- 638	
NO LOG			

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS

INVOICE