

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-05392-00-00  
Spot: NENWSW Sec/Twnshp/Rge: 32-13S-19W  
2310 feet from S Section Line, 4290 feet from E Section Line  
Lease Name: GUS RIEDEL Well #: 11  
County: ELLIS Total Vertical Depth: 3818 feet

Operator License No.: 30606  
Op Name: MURFIN DRILLING CO., INC.  
Address: 250 N. WATER, STE 300  
WICHITA, KS 67202

L1 Size: 5.5 feet: 1710 w/200 sxs cmt  
PROD Size: 7 feet: 3808 w/175 sxs cmt  
SURF Size: 10.75 feet: 254 w/250 sxs cmt

4124<sup>09</sup>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/31/2004 10:00 AM  
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.  
Proposal Rcvd. from: MARK ROBBEN Company: MURFIN DRILLING CO., INC. Phone: (785) 483-5371

Proposed Plugging Method: Ordered out 210 sxs 60/40 pozmix - 10% gel - 500# hulls - 32 sxs gel.  
Casing squeezed at 1478' - 200'.  
Annulus filled with Kempac from 1484' to surface.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 03/31/2004 2:30 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Hooked up to 10 3/4" x 7" annulus - mixed and pumped 10 sxs cement.  
S.I.P. 1500#.  
TIH with tubing to 3800' - mixed and pumped 30 sxs gel followed with 50 sxs cement with 300# hulls.  
Pulled up to 1550' - circulated cement with 100 sxs cement and 200# hulls.  
POOH. Topped with 15 sxs cement.  
S.I.P. 500#.

Perfs:

Top	Bot	Thru	Comments
3801	3813		

RECEIVED  
APR 06 2004  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed Jay Pfeifer (TECHNICIAN)

INVOICED

DATE 4-6-04

WELL NO. 2004061394

APR 01 2004

TEXAS COMPANY

#11

REIDEL

32-13-19W  
NE NW SW

35

Contr.

ELLIS

County

E 2199

Comm.

Comp.

1-2-53

IP

456 BOPD

PHY POT

Tops	Depth	Datum
TOP	3195	= 996
HEEB	3447	= 1248
LANS	3491	= 1292
ARB	3797	= 1598
TD	3818	= 1619

Casing

10" 254

7" 3808

DP: CO<sub>2</sub> 18 BOPH/14

HRS: DD 3811, GOOD

SAT 3811-14, SO

CO: DD 3818, 61 BOPH

IRVIN POOL


INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS