

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-169-19001-00-01
Spot: SWSE Sec/Twnshp/Rge: 5-16S-3W
660 feet from S Section Line, 1980 feet from E Section Line
Lease Name: APPLEQUIST A Well #: 1
County: SALINE Total Vertical Depth: 3595 feet

Operator License No.: 32495
Op Name: EDWARDS, JACK DBA EDWARDS OIL
Address: P.O. BOX 961
MCPHERSON, KS 67460

PROD Size: 5.5 feet: 3588
SURF Size: 8.625 feet: 490

11684

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/22/2004 5:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 562-8088

Proposed
Plugging
Method:

Sand to 3300'. Cap with 5 sxs cement. Shoot pipe for recovery. Perfs 3363' - 3368'.

Plugging Proposal Received By: RALPH TITTEL
Date/Time Plugging Completed: 03/23/2004 4:30 PM

WitnessType: COMPLETE (100%)
KCC Agent: RALPH TITTEL

RECEIVED
KCC DISTRICT #2

Actual Plugging Report:

Perfs:

APR 5 2004

Sanded to 3300' and capped with 5 sacks of cement. 5-1/2" casing parted at 2000'. Spotted 35 sacks at 2000' through 5-1/2" casing. Circulated cement from 550' to surface through 5-1/2" casing. Topped off -- cement stayed.

WICHITA, KS

Recovered 2000' of 5-1/2" casing.

180 sacks of 60/40 posmix with 4% gel.

Remarks: ALLIED #15000

Plugged through: CSG

District: 02

Signed

Ralph Tittel

(TECHNICIAN)

INVOICED
DATE 4-6-04
INV. NO. 2004061390