

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-167-22548-00-00  
Spot: SESWSW Sec/Twnshp/Rge: 35-15S-12W  
330 feet from S Section Line, 4290 feet from E Section Line  
Lease Name: SIEFERS A Well #: 3  
County: RUSSELL Total Vertical Depth: 3422 feet

Operator License No.: 33382  
Op Name: ALBERT W. BORELL ESTATE  
Address: P. O. BOX 399  
WILSON, KS 67490

PROD Size: 5.5 feet: 3413 w/100 sxs cmt  
SURF Size: 8.625 feet: 545 w/260 sxs cmt *# 111 22*

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/22/2004 10:00 AM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: BILL SIEFERS Company: ALBERT W. BORELL ESTATE Phone: (785) 658-3553

Proposed  
Plugging  
Method:

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 03/22/2004 11:00 AM KCC Agent: CASE MORRIS

Actual Plugging Report:

Perfs:

Tied onto 5 1/2" and pumped 280 sxs 60/40 pozmix - 10% gel cement with 500# hulls.  
Max. P.S.I. 800#. S.I.P. 400#.  
Pumped 45 sxs cement down backside.  
Max. P.S.I. 400#. S.I.P. 100#.

RECEIVED  
APR 06 2004  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

*JD*

Signed *Case Morris*  
(TECHNICIAN)

INVOICED

DATE 4-6-04

INVOICE NO. 2004061387

Form CP-2/3

APR 02 2004

ALBERT W. SORELL  
P.O. BOX 158  
WILSON, KS 67490

REPLACEMENT CARD  
#3 'A' SIEFERS  
55-15-12W  
SE SW SW

CONTR RED TIGER DRILLING  
CITY RUSSELL

GEOL JAMES W. SCHMIDT  
FIELD DUBUQUE EXT (1/4 E)

ELV 1890 KB SPD 1/7/85  
1885 GL DRLG COMP 1/18/85  
API 15-167-22,548

CARD ISSUED 4/25/85  
IP P 20 BOPD, TR WTR  
LKC 3217-3218

+	+
+	+
+	+
+	+

SMP	Tops	Depth/Datum	
			8 5/8 " 545 / 260SX, 5 1/2 " 3413 / 100SX NO CORES
TOP		2717- 827	DST (1) 3070-3080 (LKC) / 15-30-15-30, REC 5' M, SIP NA, (NOT RECORDED FSIP 457#, FP NA, FFP 90-103#, HP 1706-1270#
HEEB		2963-1073	DST (2) 3221-3242 (LKC) / 30-30-30-30, 1460' GIP, REC 61' HOCGM, 61' VHGO, 244' CL GSY OIL, SIP 844-818#, FP 72-85 / 103-129#, HP 1706-1655#
IATAN		3056-1166	
LANS		3072-1182	
BKC		3319-1429	DST (3) 3242-3284 (LKC) / 30-30-30-30, 10' GCM, W / OIL SPKS, SIP 657-501#, FP 66-48 / 66-61#, HP 1763-1664#
B/PENN CONG		3342-1452	
RTD		3422-1532	DST (4) 3343-3361 (B/PENN CONG) / 30-30-60-30, REC 190' TF (60'-65% M, 30% OIL, 5% W - 120' 25% OIL, 40% M, 35% W - 10'-2% OIL, 10% M, 88% W), SIP 968-909, FP 72-98 / 98-129#, HP 1784-1745#
NO LOG			MICT - CO, PF (LKC) 3217-3218, W / 3 SPF, SWB DWN, NAT; GSO, T&R, POP, P 20 BOPD, TR WTR, (GR 39°), 2/6/85

CORRECTION: 6/6/85 - CORRECTED FLD NAME - WAS WC

COPYRIGHT 1985  
INDEPENDENT OIL & GAS SERVICE, INC.  
WICHITA, KANSAS

15-167-22,548  
 15-167-22,548  
 15-167-22,548