

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-02714-00-00
Spot: NW Sec/Twnshp/Rge: 19-14S-14W
3960 feet from S Section Line, 3960 feet from E Section Line
Lease Name: MAI Well #: 4
County: RUSSELL Total Vertical Depth: 3260 feet

Operator License No.: 101
Op Name: KCC FEE FUND PLUG
Address: 130 S. MARKET
WICHITA, KS 67202

PROD Size: 5.5 feet: 3259
SURF Size: 8.625 feet: 135

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/29/2004 8:30 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed
Plugging
Method:

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/30/2004 1:00 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

Perfs:

03/29/2004 - Drilled out to 730' with bit and power swivel.
Scale, iron sulfide, etc. On steel at 730'.
Not loosing much fluid.

03/30/2004 - Circulated with 125 sxs 60/40 pozmix - 10% gel cement from 730'.
POOH.
Tied onto casing and pumped 75 sxs cement.
Max. P.S.I. 800#. S.I.P. 500#.
Pumped 50 sxs cement down backside.
Max. P.S.I. 500#. S.I.P. 300#.

RECEIVED
APR 06 2004
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

MD.

Signed _____

Case Morris

(TECHNICIAN)

APR 02 2004

J W BRADEN

#4

MAI

19-14-14W
CEN NW

Contr. _____ RUSSELL County

E 1842RB Comm. _____ Comp. 11-11-55 IP 25 BOPD

Tops	Depth	Datum
KG	3000	-1158
ARB	3259	-1417
TD	3260	-1418

Casing
8" 135
5" 3259

CO 3260: ACID 250

GORHAM POOL

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS