

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-21995-00-00
Spot: W2NENW Sec/Twnshp/Rge: 19-14S-14W
4620 feet from S Section Line, 3630 feet from E Section Line
Lease Name: MILBERGER Well #: 5
County: RUSSELL Total Vertical Depth: 3312 feet

Operator License No.: 101
Op Name: KCC FEE FUND PLUG
Address: 130 S. MARKET
WICHITA, KS 67202

PROD Size: 4.5 feet: 3309 w/125 sxs cmt
SURF Size: 8.625 feet: 420 w/225 sxs cmt

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/26/2004 8:30 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed
Plugging
Method:

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/26/2004 11:15 AM KCC Agent: CASE MORRIS

Actual Plugging Report:

Perfs:

Perforated at 450' - 900' - 1600'.
Ran tubing to 1800' - circulated with 140 sxs 60/40 pozmix - 10% gel cement with 300# hulls.
POOH. Pumped 50 sxs cement down backside.
Max. P.S.I. 500#. S.I.P. 100#.
Tied onto casing and pumped 135 sxs cement.
Max. P.S.I. 500#. S.I.P. 300#.

RECEIVED
APR 06 2004
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

MD

Signed _____

Case Morris

(TECHNICIAN)

APR 02 2004

replacement card

BARTON OIL CO
RUSSELL KS 67665

19-14S-14W
C W/2 N E NW

5 MILBERGER

site: 3-1/2 S & 2 W OF RUSSELL KS

cty: RUSSELL

API 15-167-21995

contr: EMPHASIS OIL OPER

field: GORHAM

geol:

fr date 09/16/82

spd date 10/11/82

drilg comp 10/17/82

card issued 01/06/83

last revised 04/14/97

*			

ELV: 1855 KB SMP

tops.....	depth/datum
*ANH.....	882 + 973
*B/ANH.....	914 + 941
KC.....	3013 - 1158
BKC.....	3256 - 1401
ARB.....	3262 - 1407
PBTD.....	3276 - 1421
RTD.....	3310 - 1455
LTD.....	3312 - 1457

LOGGED
*DRILLER TOP

IP status:
OIL, P 7 BO & 90 BWP, ARB 3274-3275, 11/10/82
CORRECTION: 4/14/97 - ORIG FR IN C W/2 NE NE;
CORR CSG
CSG: 8 5/8" 420 / 225 SX, 4-1/2" 3309 / 125 SX
DRLR SD ZNS: 0-40 (TOPSOIL & SD), 40-420 (W/SH)
NO CORES OR DSTS
MICT - CO, PF (ARB) 3/3274-75, GSO, NAT, POP, P 7 BO
& 90 BWP, 11/10/82

COPYRIGHT 1997
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS