

To: 6 100386  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

5-11  
API NUMBER 15- 15-039-20,853-00-00  
NE NW SW, SEC. 29, T. 1 S, R. 26 W/E  
2300 feet from S section line  
4030 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8981  
Operator: Adeco Inc. and Chambers  
Name & Address: 310 East Ash  
Oberlin, Ks. 67749

Lease Name Chambers Well # 7  
County Decatur 149.50  
Well Total Depth 4600 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 245

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Red Tiger Drilling Company License Number 5302

Address Wichita, Ks.

Company to plug at: Hour: \_\_\_\_\_ Day: \_\_\_\_\_ Month: \_\_\_\_\_ Year: 19 \_\_\_\_\_

Plugging proposal received from Bill Ayers

(company name) Red Tiger Drilling Company (phone) \_\_\_\_\_

were: Spot plugs through drill pipe w/heavy mud between all plugs.

1st plug at 2020' w/25 sks Rathole 15 sks

2nd plug at 1360' w/100 sks

3rd plug at 290' w/40 sks

4th plug at 40' w/wiper plug and 10 sks

RECEIVED  
STATE CORPORATION COMMISSION

JUL - 6 1989

7-6-89

Plugging Proposal Received by David K. Wann  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 1:15PM Day: 11 Month: May Year: 19 89

ACTUAL PLUGGING REPORT Order 190 sks 60/40 poz w/6% gel and 2 sks Celloflake/flowcel  
Hole reported plugged as above.

Remarks: Elevation: 2561'KB, Anhydrite depth : 2020' Did not penetrate Arb. Cemented by  
(If additional description is necessary, use BACK of this form.) Halliburton .

INVOICED did not observe this plugging.

DATE 7-7-89  
INV. NO. 25223

Signed David K. Wann  
(TECHNICIAN)

David K. Wann