

6 041138

1-30

039-20,862-06-00

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-  
C SE NW, SEC. 29, T 1 S, R 26 W/E

3300 360 feet from S section line  
3300 2587 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8981

Lease Name Chambers Well # 8

Operator: Adeco Inc. and Chambers

County Decatur 122.20

Name & Address 310 E. Ash

Well Total Depth 3760 feet

Oberlin, Ks. 67749

Conductor Pipe: Size - feet -

Surface Casing: Size 8 5/8 feet 226' w/155 cwc

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Red Tiger Drilling Co. License Number

Address Wichita, KS

Company to plug at: Hour: 12:25 AM Day: 30 Month: Jan Year: 19 90

Plugging proposal received from Bill Ayres

(company name) Red Tiger (phone)

were: Order 190 sks cement 60/40 poz 6% gel w/1/4# f.c.

Heavy mud between all plugs.

Pump cement down drill pipe

Elev. 2568 Anhy 2012-42  
Top Dakota 1500

Plugging Proposal Received by Dennis L. Hamel (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 12:25 AM Day: 30 Month: Jan Year: 19 90

ACTUAL PLUGGING REPORT 25 sks at 2030' Anhy

100 sks at 1350

40 sks at 260

10 sks at 40'

15 sks in rathole

Received 2-25-1990

Remarks: Halliburton Cementing Co.

(If additional description is necessary, use BACK of this form.)

INVOLGED

DATE 2-26-90

Signed Dennis L. Hamel (TECHNICIAN)

INV. NO. 27558

1-30