

4-14

4-061067

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-039-20,903 ⁰⁰⁻⁰⁰
110'NW of
SE SE NW /4 SEC. 29, 01 S, 26 W
3040 feet from S section line
3055 feet from E section line

Operator license# 8981

Lease L&A Chambers Trust Well # 1

Operator: Adeco Inc. & Chambers

County: Decatur 119.73

Address: 310 E. Ash
Oberlin, Kansas 67749

Well total depth 3684 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 241 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Murfin Drilling Company, Inc. License# 30606

Address: Wichita, Kansas 67202

Company to plug at: Hour: 6:00 P.M. Day: 14 Month: April Year: 1997

Plugging proposal received from: Keith VanPelt

Company: Murfin Drilling Company, Inc. Phone: _____

Were: Order 190 sxs 60/40 posmix - 6% gel with 1/4# floseal per sack.
Space all plugs with heavy drilling mud through drill pipe.

RECEIVED
KANSAS CORP COMM
1997 APR 21 P 1:17

4-21-1997

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All[], Part[], None[]

Completed: Hour: 8:45 P.M., Day: 14, Month: April, Year: 1997


Actual plugging report: _____

- 1st. Plug at 2000' w/25 sxs. Anhydrite 1980' - 2009'.
- 2nd. Plug at 1325' w/100 sxs. Dakota 1025' - 1326'.
- 3rd. Plug at 295' w/40 sxs. Surface pipe 241'.
- 4th. Plug at 40' w/10 sxs.
- 15 sxs in rathole.

Remarks: Allied Cementing.

Condition of casing(in hole): GOOD BAD _____ Anhy.plug: YES NO _____
Bottom plug(in place): YES _____, CALC _____, NO Dakota plug: YES NO _____
Plugged through TUBING _____, CASING _____. Elevation: 2525 GL

I did not observe the plugging.


(agent)
Form CP-2/3

INVOICED

DATE APR 22 1997

INV. NO. 47973

4-14 JUN 17 1997