

6 030926

8-12-87 15-039-20231-00-0932 R
API NUMBER 15- NA 1979

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

N/2 NW NE, SEC. 32, T 1 S, R 26 (W/E)
4950 feet from S section line
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5393

Lease Name Brunk Well # 1

Operator: A. L. Abercrombie Inc.

County Decatur 11625

Name & Address 802 Union Center Bldg.

Well Total Depth 3577 feet

Wichita, Kansas 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 217'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Chase, Kansas

Company to plug at: Hour: AM Day: 12 Month: August Year: 19 87

Plugging proposal received from Mark

(company name) Kelso (phone)

were: 8 5/8" set at 217' w/150 sks. 5 1/2" set at 3378' w/150 sks.

Perf 3324 - 3341. Order sand and Common Cmt. Shoot and pull pipe.

Order 200 sks 65/35 Pozmix 10% Gel 2% Dicl Cmt. Blend 5 sks Hulls.

B. J. Titan Cmt. Co. Larue Water Trucks.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour 9:45 AM Day: 12 Month: August Year: 19 87

ACTUAL PLUGGING REPORT

Sand bottom to 3150' w/5 sks Com. Cmt. on sand w/bailer.

6 shots at 1800' 1600' 1400' 1200' 1000' and 900'. Recovered 900' of 5 1/2 csg.

Squeezed 8 5/8" csg w/140 sks cmt. blend w/5 sks Hulls mixed in.

Max. Psi. 1000# close in 750#. Plug complete.

Remarks:

(If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

DATE 9-4-87

Signed Carl Goodrow (TECHNICIAN)

INV. NO. 18048