

To: **6 070790**  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

*8-13*  
API NUMBER 15- 039-20,855-00-00  
W/2 SE SW, SEC. 32, T 1 S, R 26 W/2

TECHNICIAN'S PLUGGING REPORT

Operator License # 5393  
Operator: A. L. Abercrombie Inc.  
Name & Address 150 N. Main #801  
Wichita, Ks. 67202  
Jack Partridge

660 feet from S section line  
3560 feet from E section line  
Lease Name Summer Construction 1  
Well # 114.40  
County Decatur  
Well Total Depth 3520 feet  
Conductor Pipe: Size 0 feet  
Surface Casing: Size 8 5/8 feet 281

Abandoned Oil Well  Gas Well  Input Well  SWD Well  O&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Abercrombie Drilling Inc. License Number 5393

Address 150 N. Main #801 Wichita, Ks. 67202

Company to plug at: Hour: AM Day: 13 Month: August Year: 19 89

Plugging proposal received from Bill Craig

(company name) Abercrombie Drilling Inc. (phone) \_\_\_\_\_

were: 8 5/8" 281' S.P. cwc w/200 sks 60/40 poz 2% gel 3% ca cl. By B. J. Titan.

K.C. well; Elev. 2597'; anhy 2025'; No circ bbls; Mud cond 50 vis. 9.2 weight; 9.9 water loss. Proposal 205 sks 60/40 poz 6% gel 3% cal cl and 8 5/8" plug. Spot with drill stem, circulate 42-45 vis. Mud between all plugs. 30 sks at 2035' - 100 sks w/1 sk f.c. at 1397' 50 sks at 330' 10 sks at 40' 15 sks rathole (cir) 15 sks mousehole (cir)

Plugging Proposal Received by *MJS* Marion J. Schmidt (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 1:00PM Day: 13 Month: August Year: 19 89

ACTUAL PLUGGING REPORT Abercrombie ordered 205 sks 60/40 poz 6% gel

3% cal cl and 8 5/8" plug. Spotted with drill stem, circulated, heavy mud between all plugs.  
1st plug at 2035' w/30 sks cement 15 sks rathole (cir)  
2nd plug at 1397' w/100 sks w/1 sk f.c. 15 sks mousehole (cir)  
3rd plug at 300' w/50 sks cement  
Cemented by B. J. Titan  
4th plug at 40' plug w/10 sks cement

Remarks: \_\_\_\_\_  
(If additional description is necessary, use BACK of this form.)

**INVOICED**  
to observe this plugging.

DATE 8-30-89  
INV. NO. 25743

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 28 1989  
Signed *Marion J. Schmidt*  
TECHNICIAN  
Marion J. Schmidt  
KANSAS  
8-28-89