

4 060016

8

9-26

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-039-20,856-00-00

SW SW SW, SEC. 32, T 1 S, R 26 WEX

330 feet from S section line

4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5393

Lease Name Claussen Well # 2

Operator: A.L. Abercrombie, Inc.

County Decatur 117.33

Name & Address 150 N. Main, Suite 801

Well Total Depth 3610 feet

Wichita, KS 67202

Conductor Pipe: Size 2 1/2 feet

Surface Casing: Size 8 5/8" feet 256

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A xxxxxx

Other well as hereinafter indicated _____

Plugging Contractor Abercrombie Drilling Co. License Number 5422

Address Wichita, KS

Company to plug at: Hour: 10:45 AM Day: 26 Month: Sept. Year: 1989

Plugging proposal received from Harold Maley

(company name) Abercrombie Drilling Co. (phone) 316-262-1841

were: ~~Space all plugs with heavy drilling mud and through drill pipe.~~

20 sxs. at 2075' Andydrite 2056-2085 Order 185 sxs. 60/40 pos 6% gel

100 sxs. at 1405' Dakota 1104-1404 1/4# floccel per sx.

40 sxs. at 305' 8 5/8" set at 256'

10 sxs. at 40' with wiper plug 15 sxs. in rathole

Plugging Proposal Received by Herb Deines (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None xxxxxx

Operations Completed: Hour: 10:45 AM Day: 26 Month: Sept. Year: 1989

ACTUAL PLUGGING REPORT 20 sxs at 2075'

100 sxs at 1405'

RECEIVED
STATE CORPORATION COMMISSION
OCT 20 1989

40 sxs at 305'

10 sxs at 40'

10-20-1989 15 sxs. in rathole

Remarks: B-J Titan

(If additional description is necessary, use BACK of this form.)

INVOICED ~~XXXX~~ / Will not serve this plugging.

DATE 10-24-89

INV. NO. 26207

Sub 5

Signed *Herb Deines*
(TECHNICIAN)
Herb Deines