

15-039-20231-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER _____

LEASE NAME Brunck

WELL NUMBER #1

_____ Ft. from S Section Line

_____ Ft. from E Section Line

N1/2 NW NE

SEC. 32 TWP. 1 RGE. 26W (E) or (W)

COUNTY Decatur

Date Well Completed _____

Plugging Commenced 8-5-87

Plugging Completed 8-12-87

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR A.L. Abercrombie, Inc.

ADDRESS Rt. 1 Box 56

Great Bend, Kansas 67530

PHONE# (316) 793-8186 OPERATORS LICENSE NO. 5393

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? Dist. #6 Hays, Kansas

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom T.D. 3577'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	217'	none
				5-1/2"	3378'	911'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Plugged off bottom with sand to 3150' and 5 sacks cement. Shot pipe @ 1828', 1640', 1412', 1225', 1035', 911', pulled a total of 19 joints of 5-1/2" casing. Plugged surface with 3 hulls, 140 sacks econolite w/ 2 sacks hulls mixed in. Max Press 1000#, 750# shut in. Plugging Complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling, Inc. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso, Vice-President

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Mike Kelso


(Address) P.O. Box 347

Chase, Kansas 67524

SUBSCRIBED AND SWORN TO before me this 20th day of August, 1987

Jane Hoover
Notary Public

My Commission Expires:



8-21-1987
Form CP-4
Revised 07-86

CONTRACTOR'S WELL LOG

15-039-20231-00-00

OPERATOR: Abercrombie Drilling, Inc.
 CONTRACTOR: Abercrombie Drilling, Inc.
 WELL NAME: BRUNK #1
 LOCATION: N/2 NW/4 NE/4, Sec. 32-1S-26W
 Decatur County, Kansas
 GEOLOGIST: Robert E. McCann
 SPUD DATE: March 29, 1972
 COMPLETION DATE: April 6, 1972

0	63	Clay
63	75	Flint
75	1000	Shale
1000	1100	Sand
1100	1275	Shale
1275	1435	Sand
1435	1926	Shale
1926	1955	Anhydrite
1955	2385	Shale
2385	2620	Shale & Lime Streaks
2620	3095	Lime & Shale
3095	3480	Lime
3480	3577	Lime & Shale
	3577	Rotary Total Depth

Drilled 22' of surface hole. Set 8-5/8" csg. at 217' w/150 sx. cement. Cement circulated. Plug was down at 4:00 p.m. 3-29-72. Set 5 1/2" csg. at 3378' cemented w/50 sx. 50/50 posmix w/2% gel, 12 lbs. gilsonite per sack and 100 sx. common cement w/10% salt, 2% gel, 1% c.c. and 4 lbs. friction reducer. Job completed at 6:00 a.m. 4-6-72.

ELECTRIC LOG TOPS		ELEVATION
Anhydrite	1928 (+ 552)	2480 K.B.
B/Anhydrite	1956 (+ 524)	2478 D.F.
Heebner	3221 (- 741)	2472 G.L.
Toronto	3256 (- 776)	
Lansing	3266 (- 786)	
B/K.C.	3466 (- 986)	
Granite Wash	3564 (-1084)	
ELTD	3577 (-1097)	

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

Jerry A. Langrehr, Vice President of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the BRUNK #1, N/2 NW/4 NE/4, Section 32-1S-26W, Decatur County, Kansas.

ABERCROMBIE DRILLING, INC.

By: Jerry A. Langrehr
 Jerry A. Langrehr, V.P.

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of this 18th day of April, 1972.

Beverly Mann
 Beverly Mann, Notary Public



MAR 26 1987