

15-039-20263-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION


Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
P. O. Box 17027  
Wichita, Kansas 67217  
NORTH

WELL PLUGGING RECORD

Decatur County, Sec. 32 Twp. 1S Rge. (E) 26 (W)

Location as "NE/CNW/SW" or footage from lines. E/2 SW/4 NW/4  
Lease Owner: Abercrombie Drilling, Inc.  
Lease Name: POWELL Well No. 2  
Office Address: 801 Union Center, Wichita, Kansas 67202  
Character of Well (completed as Oil, Gas or Dry Hole): Dry Hole  
Date well completed: April 21, 19 73  
Application for plugging filed (verbally): April 21, 19 73  
Application for plugging approved (verbally): April 21, 19 73  
Plugging commenced: April 21, 19 73  
Plugging completed: April 21, 19 73  
Reason for abandonment of well or producing formation: Dry Hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well: Leo Massey  
Producing formation: Depth to top: Bottom: Total Depth of Well: 3700 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

1st plug set at 1545' w/60 sx. cement  
2nd plug set at 215' w/20 sx. cement  
3rd plug set at 40' w/10 sx. cement  
Job completed at 1:00 a.m. 4-21-73.

RECEIVED  
STATE CORPORATION COMMISSION  
APR 24 1973  
4-24-1973  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor: Abercrombie Drilling, Inc.  
Address: 801 Union Center, Wichita, Kansas 67202

STATE OF KANSAS COUNTY OF SEDGWICK, ss.  
Jerry A. Langrehr (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jerry A. Langrehr  
801 Union Center, Wichita, Kansas 67202  
(Address)

SUBSCRIBED AND SWORN TO before me this 23rd day of April, 19 73

My commission expires February 10, 1975

Beverly Mann  
Beverly Mann  
Notary Public.

CONTRACTOR'S WELL LOG

15-039-20263-00-00

OPERATOR: Abercrombie Drilling, Inc.  
 CONTRACTOR: Abercrombie Drilling, Inc.  
 WELL NAME: POWELL #2  
 LOCATION: E/2 SW/4 NW/4 Sec. 32-1S-26W  
 Decatur County, Kansas  
 GEOLOGIST: Jack K. Wharton  
 SPUD DATE: April 14, 1973  
 COMPLETION DATE: April 21, 1973

0	190	Clay & Sand
190	850	Shale
850	2027	Shale & Sand Streaks
2027	2055	Anhydrite
2055	2375	Shale
2375	3275	Lime & Shale
3275	3700	Lime
	3700	Rotary Total Depth

Drilled 227' of 12½" surface hole. Set 8-5/8" surface csg. at 225' K.B. w/170 sx. cement. Cement circulated. Plug was down at 7:15 p.m. 4-14-73.  
 Dry and Abandoned

<u>SAMPLE TOPS</u>		
Anhydrite	2027	(+ 551)
B/Anhydrite	2055	(+ 523)
Heebner	3324	(- 746)
Toronto	3356	(- 778)
Lansing	3366	(- 788)
B/K.C.	3570	(- 992)
Granite Wash	3692	(-1114)
RTD	3700	(-1122)

<u>ELEVATION</u>
2578 K.B.
2576 D.F.
2570 G.L.

RECEIVED  
 STATE CORPORATION COMMISSION

APR 24 1973  
 4-24-1973  
 CONSERVATION DIVISION  
 Wichita, Kansas

STATE OF KANSAS )  
 ) SS  
 COUNTY OF SEDGWICK )

Jerry A. Langrehr, Vice President of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the POWELL #2, E/2 SW/4 NW/4 Section 32-1S-26W, Decatur County, Kansas.

ABERCROMBIE DRILLING, INC.

By: Jerry A. Langrehr  
 Jerry A. Langrehr  
 Vice President

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of this 23rd day of April, 1973.

Beverly Mann  
 Beverly Mann, Notary Public

My Commission Expires:

February 10, 1975