

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-039-20,855

00-00

LEASE NAME Sumner Construction

WELL NUMBER 1

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

660 Ft. from S Section Line

3560 Ft. from E Section Line

SEC. 32 TWP. 1S RGE. 26 ~~XXXXXX~~ W)

COUNTY Decatur

Date Well Completed 8-12-89

Plugging Commenced 8-13-89

Plugging Completed 8-13-89

LEASE OPERATOR A. L. Abercrombie, Inc.

ADDRESS 150 N. Main, Suite 801, Wichita, KS 67202

PHONE#(316) 262-1841 OPERATORS LICENSE NO. 5422

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 8-13-89 (date)

by State plugger, Marion Schmidt (KCC District Agent's Name).

Is AC0-1 filed? Yes If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3537'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	281'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Circulate heavy mud in hole. 1st plug from 2035' to 1915' w/30 sx. 2nd plug from 1397' to 997' w/100 sx. & 1 sack Flocel. 3rd plug from 330' to 130' w/50 sx. 4th plug from 40' to surface w/10 sx. & wiper plug. Rathole-15 sx. Mousehole-15 sx. All cement 60/40 pozmix, 6% gel, 3% cc.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Abercrombie Drilling, Inc. License No. 5422

Address 150 N. Main, Suite 801, Wichita, KS 67202

RECEIVED
STATE CORPORATION COMMISSION

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: A. L. Abercrombie, Inc.

AUG 25 1989

STATE OF Kansas COUNTY OF Sedgwick, ss.

CONSERVATION DIVISION
Wichita, Kansas

8-25-89

Jack K. Wharton (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jack K. Wharton

(Address) 150 N. Main, Suite 801
Wichita, KS 67202

SUBSCRIBED AND SWORN TO before me this 24th day of August, 19 89

My Commission Expires: May 18, 1993

Sharan J. Branstetter Notary Public

