


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

15-039-00170-00-00
WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Decatur County. Sec. 31 Twp. 1S Rge. 27 (E) W (W)
Location as "NE/CNW/SW" or footage from lines SE SE NW
Lease Owner Great Basins Petroleum Co.
Lease Name Betts Well No. 1
Office Address 1515 Mile High Center, Denver 2, Colorado
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole
Date well completed June 23, 19 57
Application for plugging filed June 23, 19 57
Application for plugging approved June 23, 19 57
Plugging commenced June 23, 19 57
Plugging completed June 23, 19 57
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Milton Galyardt
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3808 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	255	8 5/8"	255	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

From 3808' to 250' - heavy rotary mud and plug
250' to 188' - 1/2 sack hulls and 20 sacks cement
188' to 40' - heavy rotary mud and plug
40' to 6' - 1/2 sack hulls and 10 sacks cement
6' to surface - cellar

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Peel Brothers, Inc.
Address P.O. Box 88, Hoisington, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.
Peel Brothers, Inc. (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. PEEL BROTHERS, INC.

(Signature) BY: Al H. Smith
P.O. Box 88, Hoisington, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 24th day of June, 19 57

My commission expires April 27, 1960

Ruth Brack
Notary Public.
6-25-1957

PLUGGING
FILE SEC. 31 T. 1S R. 27W
BOOK PAGE 23 LINE 25

15-039-00170-00-00

DRILLERS' LOG

Company: Great Basins Petroleum Co.

SE SE NW
Sec. 31, Twp. 1S, Rge. 27W,

Farm Name: Betts Well No. 1

County: Decatur,
Kansas

Total Depth: 3808'

Comm: 6/13/57 Comp: 6/23/57
Contractor: Peel Brothers, Inc.

Elevation:

Production: Dry

Casing: 8 5/8" @ 255' cem.

Figures below indicate bottoms of formations:

Clay and sand	0 -	70
Shale		200
Blue shale		255
Shale		900
Shale and sand		985
Sand		1175
Shale and shells		1255
Sand and shale		1420
Sand		1500
Shale		1750
Red bed		1970
Red rock		1985
Anhydrite		2020
Red rock and shale		2110
Shale and red bed		2500
Shale and lime		3100
Lime		3205
Lime and shale		3275
Lime		3435
Lime and shale		3440
Lime		3593
Shale and lime		3625
Sand and shale		3800
Granite		3808
Total Depth		3808

This is to certify that the above information is to the best of our knowledge, true and correct.

PEEL BROTHERS, INC.

BY: Al H. Smith

SUBSCRIBED AND SWORN to before me this 24th day of June, 1957

My commission expires: April 27, 1960

Rich Brant
Notary Public

PLUGGING
FILED EC. 31 T. 1 R. 27W
BOOK PAGE 23 LINE 25

RECEIVED
STATE CORPORATION COMMISSION
6-25-1957
CONSOLIDATED DIVISION