

15-039-00184-00-00


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Decatur County. Sec. 33 Twp. 1S Rge. 27W (XX) (W)

Location as "NE/CNW%SW%" or footage from lines C NW NW
Lease Owner Rains & Williamson Oil Co.
Lease Name Metcalf Well No. 1
Office Address 412 Union Center, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) dry hole
Date well completed 8/11/62 19__
Application for plugging filed 8/11/62 19__
Application for plugging approved 8/11/62 19__
Plugging commenced 8/11/62 19__
Plugging completed 8/11/62 19__
Reason for abandonment of well or producing formation no oil or gas found in commercial quantities
If a producing well is abandoned, date of last production _____ 19__
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

NORTH



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	206	none
				7"	1731*	689*

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set plug @ 550* and cemented through drill pipe with 20 sacks cement. Fill hole with rotary mud to 180* and set plug and cement through drill pipe with 20 sacks. Fill hole with mud to 35* of base of cellar and set plug and hulls. Cap with 10 sacks. Plugging completed @ 7:30 AM on August 11, 1962

RECEIVED
STATE CORPORATION COMMISSION
8-16-62
AUG 13 1962
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Rains & Williamson Oil Co. 8-16-1962
Address 412 Union Center, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Wilson Rains - Partner (employee or owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Wilson Rains
Wilson Rains
412 Union Center, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 15th day of August, 19 62

My commission expires JANET JOHNSON
My commission expires Jan. 25, 1965

Janet Johnson
Janet Johnson Notary Public.



ROTARY DRILLING LOG

15-039-00184-00-00

Operator: Rains & Williamson Oil Co.
 NO. 1 METCALF
 C NW NW Sec. 33-1S-27W
 Decatur County, Kansas

Contractor: Rains & Williamson Oil
 Commenced: 7/29/62
 Completed: 8/11/62
 Remarks: set 8 5/8" surface
 at 206' with 125 sacs

FORMATIONS:

Surface Soil and Shale	30'
Sand	60'
Shale	206'
Shale & Chalk	870'
Shale	1380'
Shale Lime& Sand	1685'
Shale & Sand	1731'
Shale	1767'
Shale & Sand	2127'
Shale & Lime	2370'
Lime	2795'
Lime & Shale	3050'
Lime	3102'
Lime & Shale breaks	3260'
Lime	3263'
Granite	308 1/3'
Rotary Total Depth	3608'

RECEIVED
 STATE CORPORATION COMMISSION

AUG 16 1962

8-16-1962

CONSERVATION DIVISION
 Wichita, Kansas

We certify the above log is true and correct to the best of our knowledge and belief.

RAINS & WILLIAMSON OIL CO.

By:

Wilson Rains

Wilson Rains - Partner

Subscribed and sworn to before me a Notary Public in and for State of Kansas, County of Sedgwick this 15th day of August, 1962.

Janet Johnson
 Janet Johnson Notary Public

JANET JOHNSON

My commission expires Jan. 25, 1965.