

KANSAS

*Af*  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
10-04-1971  
OCT 4 1971  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

15-039-20217-00-00

Operator's Full Name John O. Farmer, Incorporated.

Complete Address 370 West Wichita Avenue, Russell, Kansas.

Lease Name Susie Thomas Well No. 1

Location CNE-SE Sec. 5 Twp. 1 Rge. (E) (W) 27

County Decatur Total Depth 3400'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X

Other well as hereafter indicated       

Plugging Contractor Murfin Drilling Company,

Address 617 Union Center Building Wichita, Kansas. License No.       

Operation Completed: Hour 1:30 PM Day 29 Month 9 Year 1971

The above well was plugged as follows:

254'--8 5/8" Surface casing, cement circulated with 225 Sx.  
Top of Dakota section @ 1000'.

Circulated hole with heavy mud. Pulled Dp to 1225' and displaced 100 Sx. cement thru  
DP from 1225' to 900'. Pulled DP to 275' and displaced 25 Sx. cement thru DP from  
275' to 200'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to  
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *W. B. Fisher*  
Well Plugging Supervisor

INVOICED  
DATE 10/5/71  
INV. NO. 4429-u