

KANSAS

Y
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
04-03-1972
APR 3 - 1972
CONSERVATION DIVISION
Wichita, Kansas

15-039-20228-00-00

Operator's Full Name John O. Farmer, Incorporated,
Complete Address 370 West Wichita Avenue, Russell, Kansas.
Lease Name Walters Well No. 2
Location NW-SW Sec. 4 Twp. 1 Rge. (E) (W) 27
County Decatur Total Depth 3500'
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated
Plugging Contractor Above
Address License No.
Operation Completed: Hour 7:30 PM Day 30 Month 3 Year 1972

The above well was plugged as follows:

240'--8 5/8" Surface casing, cement circulated.
Top of Dakota section @ 975'.

Circulated hole with heavy mud. Pulled DP to 1200' and displaced 110 Cu. Ft. cement
thru DP from 1200' to 875'. Pulled DP to 275' and displaced 30 Cu. Ft. cement thru
DP from 275' to 200'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *M. S. Nichols*
Well Plugging Supervisor

INVOICED

DATE 4-3-72

INV. NO. 5478-10