

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
SEP 5 05-1969
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-039-20065-00-00

Operator's Full Name Petroleum Management, Inc.

Complete Address Box 922 Great Bend, Kansas

Lease Name Kilzer Well No. 1

Location SW SE NW Sec. 3 Twp. 1 Rge. (E) (W) 27

County Decatur Total Depth 3600'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Southwest Casing Pulling Co.

Address Box 364 Great Bend, Kansas License No. 399

Operation Completed: Hour 1:30P Day 3 Month 9 Year 1969

The above well was plugged as follows:

Total Depth 3600' 8 5/8 csg set at 294' ewc 200 sk.

1/2 csg set at 3598' ew 200 sk cmt.

1/2 csg perf. (3382-3386)

Set 1/2 plug at 3300', poured 10' sd, dumped 4 sk cmt W/dump bailer. (3250-3290)

Cutoff and recovered 1270' of 1/2 csg.

Pumped thru 8 5/8 plug container with 10 sk gel W/4 sk hulls, 70 sk 50-50 poz cmt

W/6% total gel, 20 sk gel, 1 sk hulls plug and 70 sk 50-50 poz cmt W/6% total gel.

Cmt. (0-300) gel (300-1000) cmt (1000-1250) gel (1250-TD)

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 9/5/69

INV. NO. 412-W

Signed: L. F. Massey
Well Plugging Supervisor