

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-039-00175-00-00
Spot: CNENESE Sec/Twnshp/Rge: 2-1S-27W
2310 feet from S Section Line, 330 feet from E Section Line
Lease/Unit Name: WARNER UNIT Well Number: 103
County: DECATUR Total Vertical Depth: 3618 feet

Operator License No.: 31660 Conductor Pipe: Size _____ feet:
Op Name: ENERGY SEARCH OPERATING COMPANY Surface Casing: Size 8.625 feet: 318
Address: P.O. BOX 31697 Production: Size 5.5 feet: 3618
AURORA, CO 80041 Liner: Size _____ feet: _____

\$117.59

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/13/2001 12:00 PM
Plug Co. License No.: 31660 Plug Co. Name: ENERGY SEARCH OPERATING COMPANY
Proposal Rcvd. from: RAY DOROTHY Company: ENERGY SEARCH OPERATING CO Phone: (303) 344-2067

Proposed Plugging Method: Order 250 sxs 60/40 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received By: CARL GOODROW Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 09/13/2001 1:00 PM KCC Agent: CARL GOODROW

Actual Plugging Report:

8 5/8" set at 318' w/250 sxs cwc. 5 1/2" set at 3618' w/200 sxs.
D.V. at 1990' cwc.
Prod Perfs 3264' - 3274'; 3381' - 3392'.
Squeezed 5 1/2" with 265 sxs cement blend with 500# hulls to Max. P.S.I. 250#. S.I.P. 150#.
Plug complete.

Remarks: LEASE ALSO KNOWN AS SATER #3. ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed Carl Goodrow

(TECHNICIAN)

RECEIVED
09-26-2001
SEP 26 2001

INVOICED

DATE 9-26-01

Form CP-2/3

KCC WICHITA

INV. NO. 2002060638

SEP 17 2001

CITIES SERVICE OIL COMPANY #3 SATER

2-1-27W
NE NE SE

Contr. LOHMANN-JOHNSON DECATUR County

E 2586 Comm. 9-10-56 Comp. 10-12-56 IP 76 BOPD

Tops	Depth	Datum
TOP	3107	- 521
HEEB	3230	- 614
LANS	3268	- 682
B/KC	3182	- 896
PENN SND	3185	- 899
GRAN WSH	3602	-1016
TD	3620	-1034

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

Casing

8" 318

5" 3620

DST 3268- 80/1 HR, 80' MUD, BHP 1040#

DST 3300-25/1 HR, 4' MUD, BHP 30#

DST 3344-70/1 HR, 8' MUD, BHP 0#

DST 3385-3405/1 HR, 105' 0, BHP 1060#

DST 3429-40/1 HR, 2' MUD, BHP 0#

DST 3451-65/1 HR, 3' MUD, BHP 0#

DST 3478-95/1 HR, 150' OIL, 65' HOCM

BHP 860#

PERF 33/3483-91: PMP 41 B0 & 26 BW/24

WARNER POOL HRS
