

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-039-00176-00-00  
Spot: CSESENE Sec/Twnshp/Rge: 2-1S-27W  
2970 feet from S Section Line, 330 feet from E Section Line  
Lease/Unit Name: KILZER Well Number: 1  
County: DECATUR Total Vertical Depth: 3500 feet

Operator License No.: 31274  
Op Name: HRBEK, R.L.  
Address: RR 1, BOX 11  
MERINO, CO 80741

Conductor Pipe: Size feet:  
Surface Casing: Size 8.625 feet: 286  
Production: Size 5.5 feet: 3500  
Liner: Size feet:

\$113.75

Well Type: OIL UIC Docket No: Date/Time to Plug: 05/24/2001 12:00 PM

Plug Co. License No.: 31664 Plug Co. Name: NORTHWEST WELL SERVICE, INC.

Proposal Rcvd. from: JIM Company: NORTHWEST WELL SERVICE, INC. Phone: (970) 522-4115

Proposed Plugging Method: Order 9 yards Redi-Mix.

Plugging Proposal Received By: CARL GOODROW

Witness Type: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 05/24/2001 1:00 PM

KCC Agent: CARL GOODROW

Actual Plugging Report:

8 5/8" set at 286' cwc. 5 1/2" set at 3500'.  
Prod. Perf 3465' - 3472'. Exempt area.  
Three shots recovered 600' of 5 1/2".  
Filled hole with 9 yards Redi-Mix.  
Fluid level at 2900'.

INDEXED  
DATE 6-6-01  
NO. 2001061895

RECEIVED  
KANSAS CORPORATION COMMISSION  
06-06-2001  
JUN 6 2001

CONSERVATION DIVISION

Remarks: EMERGENCY PLUG WITH RIG OVER THE HOLE.

Plugged through: CSG

District: 04

Signed Carl Goodrow  
(TECHNICIAN)

ND

MAY 30 2001

JOE ROTHMEIER

#1 KILZER

2-1-27M  
SE-SE-NE

SAUVAGE & DUNN DRLLG

DECATUR County

Contr.

E 2590RB Comm.

1-25-57 IP 57 BOPD/KC  
PHY POI

Tops	Depth	Datum	Casing
ANH	1957	633	8" 286
			5" 3500
TOP	3127	-537	DST 3281-3304/1 HR, 80' H OCM
LANS	3280	-690	BHP 675#
B/KC	3485	-895	DST 3385-3410/1/2 HR, 10' MUD
			BHP 890#
			DST 3461-76/1 HR, 2050' GSY
			OIL, BHP 1150#
TD	3500	-910	WARNER N PERF 44/3465-72 2200' OIH/1 1/2 HRS

+	+	+	+
+	+	+	+
+	+	+	+
+	+	+	+

INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS