

4 060028

11-1213-039-20859-00-00
RECEIVED
STATE CORPORATION COMMISSION
NOV 20 1989
CONSERVATION DIVISION
Wichita, Kansas

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-039-20,859
SE SW SE, SEC. 34, T1
330 feet from S section line
1650 feet from W section line

TECHNICIAN'S PLUGGING REPORT

Operator License #9953
Operator: Harris Oil & Gas
Name & Address: 1775 Sherman St. Suite 2990
Denver, CO 80203

Lease Name Tolle Well # 2-34
County Decatur
Well Total Depth 3750 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 274

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A XXXXXX

Other well as hereinafter indicated _____

Plugging Contractor Murfin Drilling Co License Number 6033

Address Wichita, KS

Company to plug at: Hour: 2:15PM Day: 12 Month: November Year: 19 89

Plugging proposal received from Keith VanPelt

(company name) Murfin Drilling Co (phone) 316-267-3241

were: Space all plugs with heavy drilling mud through drill pipe.

Order 205 sxs. of 60/40 pos 6% gel w/ flocc per sx.

Plugging Proposal Received by Herb Deines (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None XXXXXXXX

Operations Completed: Hour: 2:15PM Day: 12 Month: November Year: 19 89

ACTUAL PLUGGING REPORT 1st plug at 3690' with 20 sxs. Arbuckle at 3690'
2nd plug at 2050' with 20 sxs. Anhydrite 2033-2063'
3rd plug at 1335' with 100 sxs. Dakota 1035-1335'
4th plug at 325' with 40 sxs. Surface pipe to 274'
5th plug at 40' with 10 sxs. wiper plug at 40'
rathole with 15 sxs.

Remarks: Allied Cementing (If additional description is necessary, use BACK of this form.)

INVOICED (If additional description is necessary, use BACK of this form.)

DATE 12-4-89
INV. NO. 26557

Signed Herb Deines (TECHNICIAN)