

6 050180

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-03920761-00-00  
S. 21, T. 1, R. 27

330 feet from S section line

990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5146

Lease Name Metcalf Well # 9 1

Operator: Rains & Williamson Inc.

County Decatur 113.10

Name & Address 435 Page Court

Well Total Depth 3480 feet

220 West Douglas

Conductor Pipe: Size \_\_\_\_\_ feet

Wichita Kans 67202

Surface Casing: Size 8 5/8 feet 230

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Rains & Williamson License Number 5146

Address 220 West Douglas Wichita Kans 67202

Company to plug at: Hour: \_\_\_\_\_ Day: \_\_\_\_\_ Month: \_\_\_\_\_ Year: 19 \_\_\_\_\_

Plugging proposal received from Louis Berger

(company name) Rains & Williamson (phone) 316-265-9686

were: Order 185 sac 50/50 Pz mix 6% gel, 3% cal clo 1 sac flo-cal 8 5/8 plug  
1 sac hulls. Jet pits circulate hole with heavy mud, spot all  
plugs: thru drill pipe, heavy mud between all plugs; good circulation  
and no fluid loss.

Plugging Proposal Received by Gelbert P. Leiker  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 5:45 P Day: 1 Month: April Year: 19 85

ACTUAL PLUGGING REPORT \_\_\_\_\_ 4-15-1985

1st Plug @ 1950 w/ 25 sacs.  
2nd Plug @ 1320 w/ 100 sacs and 1 sac flo-cal.  
3rd Plug @ 260 w/ 40 sacs  
4th Plug @ 40' w/ 8 5/8 Plug-1 sac hulls 10 sac cement  
Circulate 10 sac in rat hole. By Halliburton cementing Co.

RECEIVED  
STATE CORPORATION COMMISSION  
APR 15 1985  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: \_\_\_\_\_  
(If additional description is necessary, use BACK of this form.)

INVOICED (did or did not) observe this plugging.

DATE 4-18-85

Signed Gelbert P. Leiker  
(TECHNICIAN) 4-12-85

INV. NO. 7771  
4-1