

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-039-20,672 400-00

NE, Sec. 14, T 1 S, R 27 WE

330' feet from N section line

330' feet from W section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5393

Lease Name Chambers Well # 3-C

Operator: Lester Chambers
Name &
Address 310 E. Ash. Oberland, Mo. 67749

County Decatur

Well Total Depth 3665 feet

Conductor Pipe: Size _____ feet _____

Surface Casing: Size 8 5/8" feet 229

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Abercrombie Drilling, Inc. License Number 179

Address 801 Union Center Bldg., Wichita, Mo. 67202

Company to plug at: Hour: 11:00PM Day: 11 Month: 10 Year: 19 82

VERBAL PLUGGING ORDERS GIVEN TO Harold Malley

(company name) Abercrombie Drilling, Inc. (phone) 316-262-1841

were: Ordered out 140 sacks 5/8 posmix-4% Sol.-3% Cal. Cl. + 8 5/8" plug. Spot w/drill stem w/ heavy mud between all plugs. 1st plug C 2014' w/ 80 sacks. 2nd plug C 300' w/ 40 sacks, 3rd plug - solid bridge of hulls + plug C 40' w/ 10 sacks, Circulate 10 sacks in rat hole.

Signed Robert E. Schul
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 12:45AM Day: 12 Month: 10 Year: 19 82

ACTUAL PLUGGING REPORT 8 5/8" - 229' Sp. cas. w/ 185 sacks common-2% Sol.-3% Cal. Cl.

Ordered 140 sacks 5/8 posmix-4% Sol.-3% Cal. Cl. + 8 5/8" plug. Spot w/drill stem w/ heavy mud between all plugs. 1st plug C 2014' w/ 80 sacks, 2nd plug C 300' w/ 40 sacks, 3rd plug - solid bridge of hulls + plug C 40' w/ 10 sacks, Circulated 10 sacks in rat hole.

Remarks: _____

RECEIVED
STATE CORPORATION COMMISSION

OCT 19 1982
10-19-1982
CONSERVATION DIVISION
Wichita, Kansas

INVOICED
DATE 11-15-82
INV. NO. 1539-W

Signed Robert E. Schul
(TECHNICIAN)